

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 824 Survey held at London Date 7<sup>th</sup> June 22<sup>nd</sup> 1869  
 on the Briantine Conoid Master Joseph Scott  
 Tonnage 168 built at Peterhead When built 1865  
 By whom built Carnegie Owners Scott &  
 Port belonging to Peterhead Destined Voyage Perbice  
 If Surveyed Afloat or in Dry Dock Com<sup>o</sup> dry Dock & West India Docks.

1/2 time Survey

Last Survey, No. 2204 Port Aberdeen Classed J. A. I.  
 65

## REPAIRS

Stripped off the whole of the yellow metal sheathing. Scraped the outside planking bright in sections, from the gunwale down, or where necessary. - Drifted out treenails and bolts from each side. Lifted the timbers, opened air courses tw'n the clamps and spirketting, and as far as practicable, cut them out at the ends. One fifth the length of the vessel, the planks, frame timbers & at the treenail holes, openings or wherever seen, proved sound and good. - Lifted the Chain cables from the lockers. Ranged them along the Deck, and found them sufficient in size and in quantity. - Unhooking the Windlass stripped off the linings the main piece is sound. - Caulked from Keel to Gunwale watertight.

Present Condition of the

Decks	good	Treenails	where seen the samples good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from the Deck
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 2 &
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder	efficient	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	Sei & ym <sup>th</sup> When put on now	Standing & Running Rigging	"

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested.

She appears to be in good and efficient condition, and is in my opinion eligible to remain as Class'd J. A. I. And to be marked in the Reg<sup>r</sup> H. T.

The Amount of Fee.....£ : - : is received by me,

Special..... 2 : 2 :

Certificate (if required) : 2 :

Samuel Presious

Committee's Minute 29<sup>th</sup> June 1869

Character assigned

J. A. I. H. T. I.  
record 8m 1869



© 2019

Lloyd's Register  
 Foundation

LON654-0346