

REPORT of SURVEY for REPAIRS.

30624

No. in Reg. Book. 26 No. 1 Survey held at London Date, first Survey Decr 17 Last Survey Jan'y 7 1870
 on the Parque Oboyne Master James Grant
 Tonnage 445 built at Sunderland When built 1864
 By whom built Douglas Owners Moodie & Co.
 Port belonging to London Destined Voyage Cape
 If Surveyed Afloat or in Dry Dock "New Crane" Dry Dock and London Clocks.
in Time Survey.
 Last Survey, No. 28764 Port Lon. Classed 10. A. 1. c.f.
 REPAIRS, &c. 67

Stripped off the whole of the yellow metal sheathing.
 Lifted the timbers, opened the air courses, drifted out treenails, more than twelve from each side. Cut out new air courses below the hold beams, one fifth the length of the vessel. The timbers where exposed proved sound and good without exception. also the samples of treenails. and the iron bolts, from the chain plates. Scraped the planking bright in various places or where required. — and spotted the ceiling.

Lifted the chain cables from the lockers, ranged them along the deck and found them sufficient in size, and in quantity also. Unhooked the Windleys Stripped off the linings, the main piece proved sound.

Caulked from keel to metal line, Resheathed with 4th Metal on felt.

Present Condition of the

	good	Treenails where seen	good	Windlass and Capstan	in good order
Decks	"	Breasthooks and Stemson	"	Pumps	"
Waterways	"	Transoms, Pointers, and Crutches	"	Boats	"
Comings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Upper Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from the Deck "
Lower Deck Beams & Fastenings	"	Keelsons	"	Sails	"
Planksheers	"	Clamps and Shelves	"	Anchors No. of	3 & "
Sheerstrakes	"	Ceiling	"	Cables	"
Topsides	"	Rudder efficient	"	Hawsers and Warps	"
Wales	"	Copper felt 4 1/2 in When put on	now	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Caulking of	good where tested.		
Engine Room Skylights		Bottom, Deck, & Waterways			
Coal Bunker, Openings, Lids, &c.		Scuppers	good	Cargo and Main Hatchways	good
General Observations and Opinion,				Hatches	good "

She is now in good condition, and the "Half time Survey Rule" having been complied with. I am of opinion she is entitled to remain as class'd 10. A. 1. and to be marked F.T. in the Regⁿ.

The Amount of Entry Fee.....£ — : — is received by me,

Special..... 2 : 2

Certificate (if required)

Committee's Minute 14th January 1870

Character assigned



© 2021

Lloyd's Register Foundation

LN 655-0180