

30659. *Don.*

Side of Pitch Pine thro' fastened with galvanized iron bolts. nine lower fastenings in after hold on Starb^d side, seven ditto on Port side, four cross chocks and eleven after hoods of ceiling on each side of Baltic Oak. Two lengths of upper deck shelf and one length of upper deck waterway on Port side of Baltic Oak and Pitch Pine thro' fastened with galvanized iron bolts. one upper-deck beam scarphed and two renewed of Baltic Oak, Windlass new of English Oak. Added one new iron breasthook in lower hold, two iron hanging-knees to Hold Beams and one pair of diagonal riders $4 \times 1\frac{1}{2}$ in after hold all thro' fastened with Yellow Metal bolts. Thro' fastenings of Hold-Beam Shelf driven out and replaced with Yellow Metal those of the Tween deck standard-knees with galvanized iron and the whole of the chain and preventer plate bolts with iron. Added several fillings in way of each rigging of English Oak and Pitch Pine.

Retenailed from upper edge of trales to light mark with English Oak. Caulked from keel to waterway-seam and re-sheathed bottom with Yellow Metal on felt.

Mizen Mast, Mizen topmast, Fore and Main upper topmast, Yards new of Pitch and Red Pines, and the lower rigging to Fore and Main Masts new of wire.

A. H. Druce

Thos. W. Wawn



© 2021

Lloyd's Register
Foundation