

No 30770

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date 3rd June 18 69
on the bark "Ashur" Master W. P. Newman
Tonnage 460 built at Aberdeen When built 1863 - 3 mo
By whom built Dathig Owners A. Hector
Port belonging to London Destined Voyage Perian Gulf
If Surveyed Afloat or in Dry Dock Patchiff dry dock and afloat

Last Survey, No. 30770 Port London Classed 10 A 1

REPAIRS

For Damage - The Yellow Metal Sheathing stripped from fore side of Main Hatch forward. caulked from keel over all and resheathed bottom with Yellow Metal on felt. Upper deck extra fastened with galvanized iron spikes for same distance. Starboard planks on Starboard extending from third stoke down from gunwale renewed of Pitch Pine and Seal. Head. keel extra thro fastened with galvanized iron bolts Head-sails refitted and part new.

Port for Damage - One stoke of deck next waterway on each side renewed and one upper deck beam scarphed of Seal. One Hold beam clasp'd hooped. Stripped Yellow Metal Sheathing from fore side of Main Hatch aft. caulked from keel over all and resheathed bottom with Yellow Metal on felt.

Fore, and fore topsail yard and libboom new of Pine and she included in the damage.

Present Condition of the

Decks

Waterways

Comings

Upper Deck Beams & Fastenings

Lower Deck Beams & Fastenings

Planksheers

Sheerstrakes

Topsides

Wales

Plank (Bottom) and Counter

General Observations and Opinion,

Treenails

Breasthooks and Stemson

Transoms, Pointers, and Crutches

Timbers of the Frame at the openings

Ditto Ditto at other places

Keelsons

Clamps and Shelves

Ceiling

Rudder

Copper

Caulking of Bottom, Deck, & Waterways.

Windlass and Capstan

Pumps

Boats

Masts, Yards, &c.

Condition, how ascertained Examined aloft

Sails

Anchors No. of

Cables

Hawsers and Warps

Standing & Running Rigging

where seen good

where seen good

Good and sufficient

When put on new

Good where tested

The Amount of Fee.....£ 1 : - : is received by me,

Special.....£ 2 : 2 : -

Damage - 3 - 3 paid

Certificate (if required) : :

Committee's Minute

18

Character assigned



© 2021

Lloyd's Register

Foundation