

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at Londra Date, first Survey 13th April Last Survey April 14th 1870
 on the Ship Barbadian Master Robert Evans
 Tonnage 700 built at Greenock When built 1864
 By whom built Mc Millan Owners J. Kerr.
 Port belonging to Greenock Destined Voyage Cardiff
 If Surveyed Afloat or in Dry Dock Limehouse Dock

Last Survey, No. 2720 Port Glasgow Classed 14. A. 1. c. f.
 REPAIRS, &c. 67

Stripped off the whole of the yellow metal sheathing overhauled and made good the caulking, and sheathed with yellow metal on felt, and finding the iron cap to steering apparatus, on the Rudder head, had been working loose, and was bound up with chains in a temporary manner. - Left a Notice Card on board for the Owner. The following is an extract or copy.

"I respectfully recommend as necessary that the iron Cap to Rudder head, which is all adrift, and bound up with chains, be put to rights at once, or before she proceeds to sea."

"By giving me notice I will attend to your wishes"
 J. Kerr Esq., Greenock, 13th April 1870
 Signed Samuel Pearson

Present Condition of the Ship to and Master.

Decks	good	Freemasts	Mott's masts	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained from the Deck	"
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of 3 & 3.5	"
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder head struck from the Cap.	"	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper felt & m. When put on	"	"	Standing & Running Rigging	"
Engine Room Skylights		Caulking of	good where tested.			
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways				
Scuppers	good	Cargo and Main Hatchways	good		Hatches	good

General Observations and Opinion,

The Vessel as far as seen, appears to be in good condition, with the exception of the Rudder, and steering apparatus, at the head; - and finding she has left the River for Cardiff. - I beg to make known the same, for the information of the Committee. -

The Amount of Entry Fee.....£ : : is received by me,

Special..... 1 : 1 : 0 - Henry Rogers April 25th 1870

Certificate (if required) : :

Committee's Minute 19th April 1870

Character assigned 14th April

LON 655-0302



© 2021

Lloyd's Register Foundation


Cardiff, April 25th 1890 30799 Jan

The recommendations contained in the survey held in London on the ship "Barbadian" has been fully carried out. The Rudder Head, and the gear on Head, properly fitted and made good.

A wrought Iron hoop 8 inches wide fitted inside the Casting at Head for the gear, with four lugs at lower part, with 2 bolts in the lugs. Holes drilled in crop Head, two bolts through all, now in an efficient condition.

Henry May

Cardiff, April 25th 1890



© 2021

Lloyd's Register
Foundation