

REPORT of SURVEY for REPAIRS.

30904

No. in Reg. Book. 748 No. 30087 Survey held at London Date, first Survey 16th March Last Survey April 7th 1870
 on the Ship The Goolwa Master A. Johnson
 Tonnage 717 built at Aberdeen When built 1864
 By whom built Hall Owners Anderson &
 Port belonging to London Destined Voyage Australia
 If Surveyed Afloat or in Dry Dock Nelson Dry dock & London Docks
 Last Survey, No. 30087 Port Lon. Classed 15. A. 1. Not C. I. B. as in Regⁿ
 REPAIRS, &c. 4 69 ^{X Copper fasten's}

Entirely from damage

Hung her. and introduced three new lengths of main keel of American Rock Elm 24 in's by 16 in's. New thick garb'd lengths in wake of the foregoing New false keel throughout. Caulking made good. and Sheathing sighted and repaired. Nine of the Hold beam Stations. and two two deck Stations, straightend and refitted over the new work. and all made good and efficient as before. —


Condition of the			
	<u>good</u>	<u>Freenails bolts as far as seen good</u>	<u>Windlass and Capstan in good order</u>
Comings	"	Breasthooks and Stemson	" Pumps "
Upper Deck Beams & Fastenings	<u>firm</u>	Transoms, Pointers, and Crutches	" Boats "
Lower Deck Beams & Fastenings	"	Timbers of the Frame at the openings	" Masts, Yards, &c. "
Planksheers	"	Ditto Ditto at other places	" Condition, how ascertained <u>from the Deck</u> "
Sheerstrakes	"	Keelsons	" Sails "
Topsides	"	Clamps and Shelves	" Anchors No. of <u>34</u> "
Wales	"	Ceiling	" Cables "
Plank (Bottom) and Counter	"	Rudder <u>efficient</u>	" Hawers and Warps "
Engine Room Skylights	"	<u>Copper felt & mtl</u> When put on	" Standing & Running Rigging "
Coal Bunker, Openings, Lids, &c.	"	Caulking of	" Cargo and Main Hatchways <u>good</u> Hatches <u>good</u> .
General Observations and Opinion,	"	Bottom, Deck, & Waterways <u>good</u>	

She is in good condition, and is in my opinion entitled to remain as Classed 15. A. 1.
 Samuel Phipps

Amount of Entry Fee.....£ 2 : — : } is received by me,
 Special..... 1 : 1 : }
 Certificate (if required) — : — : }

ee's Minute 10th June 18 70
 er assigned 15 June

record damage repair
WMB



© 2021

Lloyd's Register
 Foundation
 LON 655-0374