

Half Time REPORT of SURVEY for REPAIRS.

31/50

No. _____ Survey held at London Date September 5th 1870
 on the Ship "Essex" Master Charles Hoader
 Tonnage 1255 built at Sunderland When built 1863 - 7 mo
 By whom built Marshall Owners George Marshall
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Union Dry Dock & London Dock

Survey, No. 29353 Port London Classed 13A1

Scraped bright where required, Treennails driven out as per rule, listings
 put in the hold and the frame found all good, windlass stripped, chains
 ed and all other requirements of the rules fully complied with.
 consequence of Damage, see special report.

P. Bow five bow timbers renewed with English oak, eighteen forehoods
 oak above and American elm below, ten planks of ceiling inside
 renewed with oak, also one length of shelf and one of waterway and
 beam, three iron breast hooks refitted and one staple lodging Reel.
 number of hook and Reel bolts renewed with yellow metal, the lower
 Reel repaired and about two hundred Treennails renewed on P. bow
 and three planks on same piece. Yellow metal stripped off from F.
 mast to Reel, recaulked and the metal stripped renewed on felt.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3X1X2</u>
Topsides	Ceiling	Cables <u>300</u>
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>put 684 / 70 when put on</u>	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	

This vessel being now in a good and efficient state of repair, and having fully complied
 with the rule for Half Time Survey, is eligible in my opinion to remain as
 classed

13A1

The Amount of Fee.....£ 3 : — : is received by me, and be marked (H.T. 70)

Special..... 2 : 2 : { 4/10/70

Certificate (if required) : 5 :

Committee's Minute 7th October 18 70

Character assigned 13A1 H.T. 70

Special damage £55.0



© 2021

Lloyd's Register
Foundation

LON 656-0080