

31201

REPORT of SURVEY for REPAIRS.

Change of Owners.

No. in Reg. Book. **448** No. **11** Survey held at **London** Date, first Survey **29th Jan^y** Last Survey **Feb^y 23rd 1870**
on the **Ship Chrysolite** Master **Seaward**
Tonnage **471** built at **Aberdeen** When built **1851.**
By whom built **—** Owners **J. Archibell J. Brodie**
Port belonging to **London** Destined Voyage **Mauritius**
If Surveyed Afloat or in Dry Dock **"Princes" dry dock & St Katharines**
Last Survey, No. **29351** Port **Lon.** Classed **Cons^o/65. 5 A. 1. 28**

REPAIRS, &c.

Survey'd her with a large quantity of ballast in the lower hold. Stripped off the whole of the Yellow metal Sheathing. Cleared the Keelson. Lifted the Limbers, opened the air courses tw'n decks, dub'd, scraped, and planed the outside planking bright, from the light marks upwards, including the plank sheers and waterways. Drifted out a few treenails from the bottom (6) they appeared good, —

Caulked from Keel to Gunwale, and restreath'd with Yellow metal onely.

Pointed out the requirements of the Rules {
in reference to the long Contⁿ. Please to see Letter {
from one of the Owners. But they have declined entering
into any further repairs for the {
present.

Present Condition of the

Decks	good	Treenails	where seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from the Deck "
Plank sheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors	No. of 34 "
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	fell by m ⁿ When put on	now	Standing & Running Rigging	"
Engine Room Skylights	"	Caulking of	good	"	Cargo and Main Hatchways	good
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	where tested	"	Hatches	good
Scuppers	good					

General Observations and Opinion,

I am of opinion she is eligible to remain as class'd
Cons^o/65. 5. A. 1.
Samuel Resons

The Amount of Entry Fee.....£ / : : } is received by me,
Special..... 2 : 2 : }
Certificate (if required) : 5 : }

Committee's Minute **4th November 1870**

Character assigned **Cons^o 5 A 1**



© 2021

Lloyd's Register Foundation

Chrysalis 1841

REPORT OF THE SURVEY FOR THE YEAR 1841



© 2021

Lloyd's Register
Foundation