

31228

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 128 No. 128 Survey held at London Date, first Survey Sept Last Survey 1870
on the Ship "Cardiganshire" Master J. Jenkins
Tonnage 265 built at Keyland When built 1864-9 mo
By whom built Gadorna Owners J. Jenkins
Port belonging to London Destined Voyage Cardiff & Beyerport
If Surveyed Afloat or in Dry Dock Ratchiff Dry Dock

Last Survey, No. 29526 Port London Classed 14 A1

REPAIRS, &c. For Damage cf 8.6.8

Shipped Yellow Metal sheathing, retreenails
topsides with Australian Hard Wood; caulked from keel to
fourth seam within the waterway seam, and resheathed
bottom with Yellow Metal on felt.

For Hull Sine
Holds cleared, proper stages made both inside and outside.
The timbers, and all air-courses cleared.
Outside planking scraped bright, in sandy parts.
Greenails driven out as per Rule.

Windlass unhung, wood lining's stripped, and chain-cable
ranged on deck for examination.

Retreenails from top of keels, to sixteen strakes down from same,
with Australian Hard Wood. caulked from fourth seam
within waterway to crammings.

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Examined Aloft.
Sheerstrakes	Clamps and Shelves	Sails
Topsides	Ceiling	Anchors No. of
Wales	Rudder	Cables
Plank (Bottom) and Counter	Copper <u>4 1/2 m</u> When put on, <u>horr</u>	Hawsers and Warps
Engine Room Skylights	Caulking of <u>2 good where</u>	Standing & Running Rigging
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways <u>3 tested</u>	Cargo and Main Hatchways
General Observations and Opinion,	Scuppers <u>good</u>	Hatches <u>good</u>

Is now in good, and efficient condition,
and in our opinion eligible to remain as classed and
be marked H.T. 70.

The Amount of Entry Fee.....£ 1 : - : - is received by me,
Special.....4 : 4 : -
Damage.....3 : 3 : -
Certificate (if required) 14.11.70

Committee's Minute 15th November 1870

Character assigned 14 A1 H.T. 70
record damage repair

H. Turner
W. H. H. H.
© 2021
Lloyd's Register
Foundation