

REPORT of SURVEY for REPAIRS.

31299

No. in Reg. Book. 66 No. 15 Survey held at London Date, first Survey 30th Nov^r Last Survey Dec^r 14th 18⁷⁰
 on the Ship Harkaway Master E. Corrier
 Tonnage 830 built at Dundee When built 1852
 By whom built — Owners Merch^t Ship^y Compy
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock Canal dry dock.

Last Survey, No. 15A Port — Classed Cons^d 16y. 5. A. 1.
 REPAIRS, &c. 1069

Lifted the fore, also the after piece of Main Keelson.
 which was found badly decay'd. introduced two new lengths
 of English Oak, the fore length 22 ft long. 16 ins by 20 ins. and under above
 of East India Seal, from 10 to 12 ins deep. —
 New After length 29 ft long 20 ins deep, 17 ins sided. Engl^t Oak.
 Refitted the rudder. Rebolled two iron Crutches aft. Yel^d Mess^t bolts.
 Patch'd or repaired the Yellow Metal. —
 Caulked lower cleck. and upper where required
 or necessary. —

Present Condition of the

Decks	<i>good</i>	Treenails	<i>where seen</i>	<i>good</i>	Windlass and Capstan	<i>in good order</i>			
Waterways	"	Breasthooks and Stemson		"	Pumps	"			
Comings	"	Transoms, Pointers, and Crutches		"	Boats	"			
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings		"	Masts, Yards, &c.	" "			
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places		"	Condition, how ascertained	<i>from the SK</i> "			
Planksheers	"	Keelsons		"	Sails	"			
Sheerstrakes	"	Clamps and Shelves		"	Anchors No. of	<i>3 & 1 S. 2 K</i> "			
Topsides	"	Ceiling		"	Cables	"			
Wales	"	Rudder	<i>efficiently</i>	"	Hawsers and Warps	"			
Plank (Bottom) and Counter	"	Copper	<i>See & when put on 1869</i>	"	Standing & Running Rigging	"			
		Caulking of	<i>good</i>						
		Bottom, Deck, & Waterways							
Engine Room Skylights		Coal Bunker, Openings, Lids, &c.		Scuppers	<i>good</i>	Cargo and Main Hatchways	<i>good</i>	Hatches	<i>good</i>

General Observations and Opinion,

She is now in good condition, and I am of opinion is
 entitled to remain as Class'd
 Cons^d 5. A. 1.
 Samuel Presons

The Amount of Entry Fee..... £ 2 : - : 7 is received by me,

Special..... 2 : 2 : {

Certificate (if required) : 5 : {

Committee's Minute 23rd Dec^r 1870

Character assigned Cons^d 5A 1

record repair



© 2021

Lloyd's Register
Foundation

LON656-0182

Haraway

REPORT of SUBMITTEE for REPAIRS.



© 2021

Lloyd's Register
Foundation