

REPORT of SURVEY for REPAIRS.

31459

No. in Reg. Book. 370 No. 1 Survey held at London Date, first Survey 25th Jan^y Last Survey 7th March 1871
 on the Ship "Shun Lee" Master John Appender
 Tonnage 674 built at London When built 1867
 By whom built Walker Owners H. Walker, Potter, Wilson & Co.
 Port belonging to London Destined Voyage New Zealand
 If Surveyed Afloat or in Dry Dock Linthouse Dry Dock and Afloat
 Last Survey, No. 30061 Port Lon. Classed 14 A 1
 REPAIRS, &c. For Damage. of 4. 59.

Stripped Yellow Metal sheathing, sixteen feet of false keel (five lengths) renewed of Rock Elm 5 in thick -
 Hung in shores caulked from keel to top of wales; and resheathed bottom with Yellow Metal on felt.

Not for Damage - The timber boards and caking equal to one stroke fore and aft on both sides in the hold below the upper turn of bilge removed.

Galvanized iron thro' fastenings of the inner skin driven out for examination and found to be in a satisfactory state.

One piece of Main keelson in midships renewed of Oak thro' fastened with Yellow Metal bolts.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>4 in</u> When put on <u>now</u>	Standing & Running Rigging
Engine Room Skylights	Caulking of <u>3 good where</u>	
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways <u>3 tested</u>	
General Observations and Opinion,	Scuppers <u>good</u> Cargo and Main Hatchways <u>good</u> Hatches <u>good</u>	

In good and efficient condition and in my opinion eligible to remain as classed and to be marked (S.S. 71)

The Amount of Entry Fee.....£ 2 : : is received by me,
 Special.....3 : 3 :
 Certificate (if required) : 5 :

Committee's Minute 7th March 1871

Character assigned 14 A 1 S.S. 71 -

Damage £ 2 - paid

31459 Lon

Main Mast topped at head and fished with Oregon
Pine. Fore and Main Yards, and two Sloop. yards
all of Pine.

W H Jones



© 2021

Lloyd's Register
Foundation