

# REPORT of SURVEY for REPAIRS.

31500

No. in Reg. Book. 332 No. 1 Survey held at London Date, first Survey 14 March Last Survey 27 March 1871  
 on the Barb' Woolhampton Master Dario Kinneer  
 Tonnage 380 built at Montrose When built 1865 & mo  
 By whom built Birnie Owners Blyth & Co  
 Port belonging to London Destined Voyage Mauritius  
 If Surveyed Afloat or in Dry Dock Union dry dock

Last Survey, No. 29934 Port Lorr. Classed 11A1

## REPAIRS, &c.

Holds cleared proper stages made both inside and outside  
 She timbers and all air courses cleared  
 Outside planking scraped bright in various parts  
 Greenails driven out as per Rule  
 Windlass unhung wood linings stopped, and chain-cables  
 ranged on deck for examination.

Stopped Yellow Metal sheathing, castings  
 have now been cut in the fore and after ends as per Deck 37  
 added three pairs of iron riders (diagonal), in the fore body  
 and three pairs in the after body extending from upper deck  
 shelf-piece to floor heads. as also one pair of vertical straps in  
 midships from Hold Beam Spirketting to within three feet of the  
 belson each 4x2 1/4 and thro' fastened with Yellow Metal Bolts  
 Hung in Shores caulked from keel to gunwale and resheathed bottom

## Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper	Standing & Running Rigging
Engine Room Skylights	Caulking of	Cargo and Main Hatchways
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways	Hatches
General Observations and Opinion,	Scuppers	

Is now in good and efficient condition  
 and in my opinion eligible to remain as classed  
 and to be marked (HT-71)

The Amount of Entry Fee.....£ 1 : - : is received by me,  
 Special.....3 : 3 :  
 Certificate (if required) : 5 :

Committee's Minute 28 March 1871

Character assigned 11A1 HT-71  
record 4M

*[Signature]*

*[Signature]*

Lloyd's Register Foundation

1030 95907