

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date, first Survey 13th May Last Survey 1871

on the S. "Durham" Master J. Kerr

Tonnage 1286 built at Pallion When built 1864

By whom built _____ Owners G. Marshall

Port belonging to London Destined Voyage _____

If Surveyed Afloat or in Dry Dock London Dock & Union dry dock

Last Survey, No. 30925 Port Lon. Classed 13 A 1

REPAIRS, &c. Scraped where required, Treennails & bolts driven out for survey (good) timbers & air courses cleared and frame found all good, Windlass unhung and stripped (good) caulking good and chains ranged - Listings cut out as per Rule -

Now done - Three upper bolts in thirteen strap (diagonal & vertical) riders renewed with galvanized iron and yellow metal. The yellow metal repaired and the ship recaulked from metal line to plank sheers -

30 fms of 1 7/8 Stud chain tested to 6 3/4 Tons at the Poplar Proving House by L R Isitt, now supplied to make up deficiency -

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Plank sheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 x 1 x 2</u>
Topsides	Ceiling	Cables <u>300 fms</u>
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>F & J M</u> When put on <u>70</u>	Standing & Running Rigging
	Caulking of	
	Bottom, Deck, & Waterways <u>good</u>	
Engine Room Skylights	Coal Bunker, Openings, Lids, &c.	Scuppers
		Cargo and Main Hatchways
		Hatches <u>good</u>

General Observations and Opinion, This vessel is now in a good and efficient state of Repair and having fully complied with the Rules is eligible in my opinion to remain as classed 13 A 1 and be marked (H.T. 70)

The Amount of Entry Fee.....£ : : is received by me, J. W. Wain
Special..... 4: 4: } 1871
Certificate (if required) : 5: }

Committee's Minute 6th June 18 71
Character assigned 13 A 1 H.T. 71