

REPORT of SURVEY for REPAIRS.

31794

No. in Reg. Book. 143 No. 31020 Survey held at London Date, first Survey July 12th Last Survey July 18th Aug 3rd 1871

on the Barque Agatha Master J. Bassian

Tonnage 421 built at Sunderland When built 1866 ^{1 msk}

By whom built Mills Owners Hankey &

Port belonging to London Destined Voyage West Indies

If Surveyed Afloat or in Dry Dock Nelson Dry dock & West India Dock,
Half Time Survey

Last Survey, No. 31020 Port Lon. Classed 13, A. 1. ^{c. 8.}
7.70

REPAIRS, &c.

Stripped off the Yellow metal Sheathing. Cleared the Hold, lifted the timbers. Open'd air courses. and cut out the listings at the ends as required by the Rules 15th her length. Scraped her bright outside in sections or where necessary. - Inside scraped and cleansed throughout. - Drifted out samples of treenails 12' from each side, and chain plate bolts. - The timbers at the openings, and treenail holes proved sound and good without exception. - Lifted the chain cables from the lockers, ranged them found them good and sufficient. - Untung and stripped linings off the Windlass. main piece is sound. - Chalk'd from Keel to Gunwale Testuash'd with Yellow metal on felt. -

Present Condition of the

Decks	good	Treenails	where seen and tested good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	"
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 3 B. 1 S. 2 K
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder	efficient	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	Self & ym When put on now	Standing & Running Rigging	"
Engine Room Skylights	"	Caulking of	good		
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	good		
Scuppers	good			Cargo and Main Hatchways	good
Hatches	good				

General Observations and Opinion,

Cleared the Hold and overhauled her throughout in unison with the "Half Time Survey" Rules Secⁿ 21, pag 7. which have been fully complied with. She is now in good condition and entitled to remain as class'd 13, A. 1.

The Amount of Entry Fee.....£

Special..... 2 : 2

Certificate (if required)

is received by me, and to be marked in the Reg^r 11, T. 1/41.

Samuel Presons

Committee's Minute

Character assigned

11th August 1871
13 A 1 HT 71
Record 4/11



© 2021

Lloyd's Register Foundation

LON 654-0022

Agatha
REPORT of SURVEY for REPAIRS.



© 2021

Lloyd's Register
Foundation