

REPORT of SURVEY for REPAIRS.

31801

No. in Reg. Book. 362 No. 362 Survey held at London Date, first Survey 20th June Last Survey June 29th 1871
 on the Ship Shannon Master N. Morder
 Tonnage 1292 built at London When built 1862
 By whom built Green Owners R & H. Green
 Port belonging to London Destined Voyage India
 If Surveyed Afloat or in Dry Dock Green's Lower Dry Dock & East India Dock
Half Year Survey.
 Last Survey, No. 30244 Port London Classed 13. A. 1.
See annual Report. 7. 69
 REPAIRS, &c.

Scraped bright the planking in sections or in various places outside, inside, from the Hold beams to the Keel. - dripped out more than twelve treenails from each side. Lifted the timbers fore and aft opened all air courses and cut out listings in unison with the Rules. The timbers where exposed proved sound and good, likewise at the treenail holes.

Memorandum The Windlass was unhooked and linings stripped last year the Chains were also lifted from the lockers, and ranged along the Deck at the same time. - see report of 1870.

Present Condition of the	Repaired the Yellow metal, and pay'd it with "Peacocks" Anti Corrosive.			
Decks	good	Treenails where seen	good	Windlass and Capstan in good order
Waterways	"	Breasthooks and Stemson	"	Pumps "
Comings	"	Transoms, Pointers, and Crutches	"	Boats "
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c. "
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained from the Deck "
Planksheers	"	Keelsons	"	Sails "
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of 3 B. 1 S. 2 H "
Topsides	"	Ceiling	"	Cables "
Wales	"	Rudder efficient	"	Hawsers and Warps "
Plank (Bottom) and Counter	"	Copper for & when put on 1868	"	Standing & Running Rigging "
		Caulking of	good	
Engine Room Skylights		Bottom, Deck, & Waterways	good	
Coal Bunker, Openings, Lids, &c.		Scuppers	good	Cargo and Main Hatchways good Hatches good

General Observations and Opinion,

Examined her inside and outside. She is now in good and efficient condition, and the Halfyear Survey Rule having been now completed, and complied with.

The Amount of Entry Fee.....£ - : - : is received by me, remain as Class'd 13. A. 1.
 Special..... 2 : 2 : and to be mark'd H.T. in
 Certificate (if required) : 5 : the Reg'n.

Committee's Minute 15th August 1871

Character assigned

13 A 1
H.T. 71



© 2021

Lloyd's Register Foundation

LON 657-0027

REPORT OF SURVEY FOR REPAIRS

Hannon



© 2021

Lloyd's Register
Foundation