

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 12 No. 3208 Survey held at London Date, first Survey 1st Nov 71 Last Survey 2nd Jan 72
 on the Barque 'Pactolus' Master Romero
 Tonnage 476 built at Palhou When built 1864 - 6 mo.
 By whom built Hill Owners Robbinston & Co
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock Both. Means' dry dock and Afloat.

Last Survey, No. 1549 Port Sw. Classed 10 A
 REPAIRS, &c. cf. 3.68

Holds cleared proper stages made both inside and outside
 The timbers and all air-courses cleared
 outside planking scraped bright in sunny parts
 Keenails driven out as per Rule.

Windlass unhung, wood linings stripped, and the chain
 cables ranged on deck for examination.

Three lower cant timbers on starboard choiced
 with English Oak. Two planks of ciching in way of same
 renewed of Dantzic Oak and Greenheart. Windlass new of
 English Oak spindle put through. Main piece

The vessel hung in shores 20 ft. 176 stow chain. Please Supp.
 "For Damage" please see other side.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper	Standing & Running Rigging
Engine Room Skylights	Caulking of	Cargo and Main Hatchways
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways	Hatches
General Observations and Opinion,		

In good and efficient condition,
 and in my opinion eligible to remain as classed.
 and to be marked H.T. 72

The Amount of Entry Fee.....£ 1 : - : is received by me,

Special..... 3 : 3 : } 23/1/72

Certificate (if required) : 5 : }

Committee's Minute 26th January 18 72

Character assigned

Record damage repair

For Damage. £ 2-2-

32081 Lon

For 'Damage'

Main piece of Rudder renewed of Eng^h Oak -
and one broken pintle (the lower one) of Yellow Metal

Stripped Yellow Metal Sheathing, caulked from
keel to lower edge of wales; and resheathed bottom
with Yellow Metal on felt.

J. W. Turner



© 2021

Lloyd's Register
Foundation