

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 806 No. 31921 Survey held at London Date, first Survey Jan 5 Last Survey Jan 29 1872
 on the B^e Swanley Master J. G. Wood
 Tonnage 351 built at Sunderland When built 1853
 By whom built Briggs Owners C. Dawson
 Port belonging to London Destined Voyage Jamaica
 If Surveyed Afloat or in Dry Dock Timehouse Dry Dock & Afloat
 Last Survey, No. 31921 Port Lon. Classed Cont 66-9 A.S. 13
 12-70

REPAIRS, &c.

The hold timbers and all air courses cleared, outside planking scraped bright in places, bolts and treenails driven out for survey (Windlass new, please see Report No 31931. Chain cables ranged on deck for examination found sufficient Stripped off all the yellow metal sheathing, retreenailed with Australian hard wood, eighteen Strakes of the planking from the gunwale down, renewed in topsides three fore hoods of planking on Starboard side and two planks on Port side aft with E. & Baltic Oak, fitted three pairs of knee riders through fastened with yellow metal bolts caulked from keel to gunwale resheathed with yellow metal on felt, removed and refitted the trawse chocks and trawsepipes.

Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	Three
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from deck
Planksheers	"	Keelsons	"	Sails	Good
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of	3 B 1 S 2 K
Topsides	"	Ceiling	"	Cables	240 Fathoms
Wales	"	Rudder	"	Hawsers and Warps	Good &
Plank (Bottom) and Counter	"	Copper <u>14 9/16</u> When put on <u>new</u>		Standing & Running Rigging	Sufficient
Engine Room Skylights		Caulking of			
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways	Good	Cargo and Main Hatchways	Good
Scuppers	Good			Hatches	Good

General Observations and Opinion,

This Vessel is now in good condition and in my opinion eligible to remain as classed and to be marked in the Register Book H. T. 72.

The Amount of Entry Fee.....£ 1 : - : is received by me,

Special..... 4 : 4 : *[Signature]*

Certificate (if required) : : : *[Signature]*

Committee's Minute 2nd February 1872

Character assigned Cont 9

HT 72

recd 9. M

Special Survey £1.1-0
[Signature]

[Signature]



© 2021

Lloyd's Register Foundation

LON 651-0240