

REPORT of SURVEY for REPAIRS.

Half Time Survey.

No. in Reg. Book. 143 No. 32145 Survey held at London Date, first Survey Jan 30th Last Survey Feb 19th 1872.
 on the "S. Carnaguen" Master M. Colville
 Tonnage 825 built at Aberdeen When built 1867-4 M^c
 By whom built Humphrey Owners Common H^c
 Port belonging to Aberdeen Destined Voyage Adelaide
 If Surveyed Afloat or in Dry Dock London Docks Afloat
 Last Survey, No. 31460 Port Lon. Classed 9A
 2, 71

REPAIRS, &c.

Now done: the hold, timbers, and all air courses, cleared and listings cut in accordance with Rule Section 37. Outside planking scraped bright in places. Bolts and treenails driven out for survey found good. Windlass stripped and unhung. And chain cables ranged on deck for examination found good and sufficient caulked from metal line to gunwale; renewed, both windlass bitts, and the planks through which they pass with Teak; the full bitt beam and the one kept abaft with P. Pine, two short shifts of deck on each side with Y. Pine. And shrank an Iron band round the rudder head.

P. J. C.

Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stenson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	Four
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from deck
Planksheers	"	Keelsons	"	Sails	Two Suits
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of	3 B. 1 S. 200
Topsides	"	Ceiling	"	Cables	300 fathoms
Wales	"	Rudder	"	Hawsers and Warps	Good &
Plank (Bottom) and Counter	Not seen	Copper	At Y. M. When put on 1871	Standing & Running Rigging	Sufficient
Engine Room Skylights		Caulking of		Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	Good	Bottom, Deck, & Waterways	Good	Hatches	Good.
Scuppers	Good				

General Observations and Opinion,

This Vessel is now in good condition and in my opinion eligible to class 10 A. and to be marked in the Register Book H.T. 1872.

The Amount of Entry Fee.....£ : : is received by me,

Special..... 6 : 6 : : 1872

Certificate (if required) : 5 : : 1872


Committee's Minute 5th March 18 72

Character assigned

Raise to 10 A. 1

H.T. 72

Lawrence
 This vessel is entitled
 the 10A 1. class. There -
 8 years Lable A
 1 year for Prop
 1 year for 3 years metal fastenings
 10 years
 1872
 4/3/72



32175 Len

The Owners have applied for an increase of classification
I find from the first Entry Report that the timber used
in his construction is suitable according to the amended
Table A for the 8 years grade. He was built under a roof
and is metal fastened.

J. Lawrence



© 2021

Lloyd's Register
Foundation