

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **149** No. **31180** Survey held at London Date, first Survey Feb 22nd Last Survey March 19th 1872
 on the "Benjamin Buck Green" Master Bowman
 Tonnage 528 built at Cowes When built 1846
 By whom built - Owners Blyths & Co
 Port belonging to London Destined Voyage Mauritius
 If Surveyed Afloat or in Dry Dock Linehouse Dry Dock & Afloat
 Last Survey, No. 31180 Port Lon. Classed E.A.S. Red
 S.S. 6% 10.70 8 ms

REPAIRS, &c.

The hold, timbers, and all air courses cleared, outside planking scraped bright in places, bolts and treenails driven out for survey found good, windlass stripped and unhung, and chain cables ranged on deck for examination found good and sufficient stripped off all the yellow metal sheathing, fitted an additional breasthook in lower hold to compensate for one found broken, caulked from keel to gunwale, and reshathed the bottom with yellow metal on felt.

Present Condition of the

Decks	Good	Treenails	When Sun good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from deck
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 3 1/2 1 1/2 2 1/2
Topsides	"	Ceiling	"	Cables	270 fathoms Green
Wales	"	Rudder	"	Hawsers and Warps	Good
Plank (Bottom) and Counter	"	Copper	At G. M. When put on	Standing & Running Rigging	Sufficient
Engine Room Skylights	"	Caulking of	"	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	Good	Hatches	Good
Scuppers	Good				

General Observations and Opinion,

This Vessel is now in good condition and in my opinion eligible to remain as classed and to be marked in the Register Book. H.T. 1872.

The Amount of Entry Fee.....£ — : — : is received by me,

Special..... 3 : 3 :

Certificate (if required) : 5 :

Committee's Minute 26th March 18 72

Character assigned As in led H.T. 72

