

REPORT of SURVEY for REPAIRS.

32297

No. in Reg. Book. *697* No. *32297* Survey held at *London* Date, first Survey *Jan 4* Last Survey *18*
 on the *B^{te} "Arcadia"* Master *J. Stopher*
 Tonnage *417* built at *Bristol* When built *1863-9 m*
 By whom built *Hill* Owners *G. Dawson*
 Port belonging to *London* Destined Voyage *West Indies*
 If Surveyed Afloat or in Dry Dock *Limehouse Dry Dock*
 Last Survey, No. *29206* Port *Lon.* Classed *14 A* *68*

REPAIRS, &c.

The hold, timbers, and all air courses cleared, and listings cut in accordance with Rule. Section 37. Outside planking scraped bright in places, bolts and trenails, driven out for survey, found good. Windlass stripped, and unhung, and chains ranged on deck for examination, found good and sufficient; stripped off all the yellow metal sheathing, caulked from steel to metal line; and resheathed the bottom with yellow metal on felt.

The Owner has applied for an increase of class, under the Mixed Material Rule. - We find from the first Entry Report, and examination of the vessel when in dry dock that the Sheerstrakes

Present Condition of the		Vessel when in dry dock that the Sheerstrakes	
Decks	Good	Treenails	Good
Waterways	"	Breasthooks and Stemson	"
Comings	"	Transoms, Pointers, and Crutches	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"
Planksheers	"	Keelsons	"
Sheerstrakes	"	Clamps and Shelves	"
Topsides	"	Ceiling	"
Wales	"	Rudder	"
Plank (Bottom) and Counter	"	Copper <i>14 9 m</i> When put on <i>now</i>	
Engine Room Skylights	"	Caulking of	
General Observations and Opinion,		Bottom, Deck, & Waterways	Good
		Windlass and Capstan	Good
		Pumps	"
		Boats	Three
		Masts, Yards, &c.	"
		Condition, how ascertained	from deck
		Sails	Two Suits
		Anchors No. of	3 B. 1 S. 2 K
		Cables	240 Fathoms
		Hawsers and Warps	Good &
		Standing & Running Rigging	Sufficient
		Cargo and Main Hatchways	Good
		Hatches	Good

This vessel is now in good condition and in our opinion eligible to remain as classed and to be marked in the Register Book H. T. 72

The Amount of Entry Fee.....£ - : - : is received by me,

Special..... 2 : 2 :

Certificate (if required) - : - :

Committee's Minute *17 May* 18 *72*

Character assigned *14 A*

And topsides, only are of Teak; the remainder
of the material being of the 12 Years grade,
We therefore respectfully beg to recommend, that
her classification remain unchanged.

Thos. W. Nawn

J. Lawrence



© 2021

Lloyd's Register
Foundation