

REPORT of SURVEY for REPAIRS.

32319

No. in Reg. Book. 8074 No. 1 Survey held at London Date, first Survey March 25 Last Survey April 27 1872
 on the Ship "Asshur" Master H. P. Newman
 Tonnage 460 built at Aberdeen When built 1863-3 M^{ts}
 By whom built Duthie Owners A. Hector
 Port belonging to London Destined Voyage Bushire
 If Surveyed Afloat or in Dry Dock Ratcliff Dry Dock & Afloat
 Last Survey, No. 31704 Port Lon. Classed 10 A. 1
 REPAIRS, &c. 5.71

For damage.

Sighted the Bottom, patched the yellow metal sheathing renewed the fore beam of main hatchway and scarphed the deck beam next forward with Dantye Oak fitted an additional pair of short hanging knees, under the hatchway beam, fitted new ceilings of Dantye Oak and refitted the main hatchway comings. renewed a portion of the deck between the fore and main hatchways with yellow pine and repaired the bulwark bulking on Port side. Caulked main deck and waterway seams, and fitted new fore Mast of Oregon Pine.

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>When run good</u>	Windlass and Capstan	<u>Good</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	<u>And</u>
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	<u>Sufficient</u>
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of	"
Topsides	"	Ceiling	"	Cables	<u>When</u>
Wales	"	Rudder	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper <u>For Y. M.</u> When put on <u>1871</u>		Standing & Running Rigging	<u>Run</u>
Engine Room Skylights	"	Caulking of			
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	<u>Good</u>		
Scuppers	<u>Good</u>	Cargo and Main Hatchways	<u>Good</u>	Hatches	<u>Coverd.</u>

General Observations and Opinion,

This vessel is now in good condition and in my opinion eligible to remain as classed.

The Amount of Entry Fee.....£ 1 : - : is received by me,

Special..... 2 : 2 :

Certificate (if required) : :

Committee's Minute 14th May 1872.

Character assigned 10 A. 1

renew damage repair