

Half Time & to raise for Mixed Materials - 32810 REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date, first Survey 2nd Dec 1872 Last Survey 10th Jan 1873
on the S "Northfleet" Master J. Oates
Tonnage 895 - 950 built at Northfleet When built 1853
By whom built _____ Owners J. Patton Junr
Port belonging to London Destined Voyage Hobart Town
If Surveyed Afloat or in Dry Dock Bullhead dry dock & S.W.S. Dock
Last Survey, No. 31076 Port London Classed 14 A 5
REPAIRS, &c. Copper Bolts CT Cont 67 - 9

Yellow metal sheathing stripped off, scraped bright where required, new listings cut out 1/5 the length of the ship on both sides and at each end and the frame found all good (except two timbers on each side forward as compensation for which a pair of diagonal iron riders have been introduced) timbers and arcades opened, copper bolts tested, Windlass unhung & stripped good, chains ranged and all other requirements complied with -

Hung on shores; caulked throughout } In Mixed Materials
and sheathed with Gal: Metal on Sels. } P. J. O.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps 2
Comings	Transoms, Pointers, and Crutches	Boats 4
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings <u>Good</u>	Ditto Ditto at other places <u>Good</u>	Condition, how ascertained <u>Report &</u>
Planksheers <u>when seen</u>	Keelsons	Sails <u>sufficient</u>
Sheerstrakes	Clamps and Shelves <u>where seen</u>	Anchors No. of <u>3 1/2</u> <u>Sufficient</u>
Topsides	Ceiling	Cables <u>300</u>
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>T & TM</u> When put on <u>now</u>	Standing & Running Rigging
Engine Room Skylights	Caulking of	
General Observations and Opinion,	Bottom, Deck, & Waterways <u>Good</u>	
	Goal Bunker, Openings, Lids, &c.	Cargo and Main Hatchways & Hatches <u>Good</u>
	Scuppers	

This vessel is now in a good and efficient state and considering her Materials I beg to recommend that her Class be raised One Year for Mixed Materials and marked HT Lon 73

The Amount of Entry Fee.....£ : : is received by me,
Special..... 6 : 6 :
Certificate (if required) : 5 :

Thos. M. Wain

Committee's Minute Jan^y 23rd 1873 18

Character assigned Raised to 15-A-1
Record 12 & 14 Years Mat
Feb 7th 1873

HT 73



© 2021

Lloyd's Register Foundation

32810. Jan.

Mixed Materials

It will be seen that the frame is of English Oak
12 yrs, Main Keelson Iron bark 12 yrs & Seat 14 yrs
Deck beams Seat 14 yrs & Mahogany 12 yrs ^{dyn in 1853} Hold
beams Seat 14 yrs English Oak & Mahogany 12 yrs
Outside planking from light mark up Seat
14 yrs Waterways Seat 14 yrs also that the
whole of the inside Ceiling clamps &c are
of Seat 14 years - She is extra fastened
and the workmanship is very good

Thos W. Wain



© 2021

Lloyd's Register
Foundation