

32985

To raise for Mixed Materials

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date, first Survey 10<sup>th</sup> March Last Survey March 13<sup>th</sup> 1873  
 on the S. Star of China Master Angus  
 Tonnage 794 built at Aberdeen When built 1862 Mo 7  
 By whom built \_\_\_\_\_ Owners H. Adamson

Port belonging to Aberdeen Destined Voyage \_\_\_\_\_

If Surveyed Afloat or in Dry Dock Regents dry dock

Last Survey, No. 22261 Port London Classed 14 A 1  
 REPAIRS, &c. Roof HT 68

Gallow metal stripped off recasked from keel to 6<sup>th</sup> Strake of deck and the Gallow-metal renewed on  
 Selt

## Mixed Materials

The frame, Stem, Knight heads, and Stern post are of English Oak 12 years; Keelson of Greenheart 12 yrs, Beams of Iron; the outside planking from light mark to trales principally Morra & Greenheart 12 yrs, the remainder Teak 14 years; Wales, Teak 14 yrs; Topsides and Sheerstrakes, Teak 14 yrs; Plank sheers in midships Teak, 14 yrs; Ends English Oak 12 yrs; Upper deck Waterways Teak 14<sup>th</sup> Shelves Clamps and lower hold ceiling Morra and Greenheart 12 yrs. Between deck ceiling Teak 14 yrs.

### Present Condition of the

Decks	Good	Treenails	good where seen	Windlass and Capstan	
Waterways	do	Breasthooks and Stenson	Good	Pumps	
Comings	do	Transoms, Pointers, and Crutches	do	Boats	
Upper Deck Beams & Fastenings	do	Timbers of the Frame at the openings	do	Masts, Yards, &c.	
Lower Deck Beams & Fastenings	do	Ditto Ditto at other places		Condition, how ascertained	
Plank sheers	do	Keelsons	do	Sails	Good &
Sheerstrakes	do	Clamps and Shelves	do	Anchors No. of	Sufficient
Topsides	do	Ceiling	do	Cables	
Wales	do	Rudder	do	Hawsers and Warps	
Plank (Bottom) and Counter	do	Copper <u>Iron</u> When put on	now	Standing & Running Rigging	
Engine Room Skylights		Caulking of			
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways	good		
Scuppers		Cargo and Main Hatchways		Hatches	good

### General Observations and Opinion,

This vessel is now in a good and efficient state; and, having a large proportion of Teak with Iron Beams; I beg respectfully to recommend her to the favourable consideration of the Committee, to be raised one year viz

The Amount of Entry Fee.....£ : : is received by me,

Special..... 5 : 5 : }

Certificate (if required) : 5 : }

Mixed Material 12 yrs  
 Metal — 1  
 Roof — 1  
 Misc Material 1

15 A 1

Committee's Minute April 10<sup>th</sup> 1873

Character assigned 15 A 1.

12 & 14 yrs mix  
 HT 1868

Thos. W. Brown

Lloyd's Register  
 Foundation