

33,211

Recd 30.7.73

Half Time Survey & Raised Class  
**REPORT of SURVEY for REPAIRS.**

No. in Reg. Book. **No.** Survey held at London Date, first Survey 31 May Last Survey 31 July 1873  
on the "S. Paramatta" Master J. Manson  
Tonnage 1591 built at Sunderland When built 1866-500  
By whom built Laying Owners Wright & Moore  
Port belonging to London Destined Voyage \_\_\_\_\_  
If Surveyed Afloat or in Dry Dock Nigram's Dry Dock & Y.N.P. Dock  
Last Survey, No. 21753 Port London Classed 13 A 1  
REPAIRS, &c. None done.

Placed on blocks in Dry Dock; the hold cleared, and stags made both inside and outside; the timbers and all air-courses cleared, and the outside planking scraped bright in several places. Treenails not less than three on each side driven out, and found good. All yellow metal bolts tested where practicable. The windlass unhooked and stripped, and the chain cables ranged on deck & found good and sufficient. Y.M. patches, and a number of studs stripped off on starboard side aft, and renewed.

At the owner's request this vessel has also been surveyed for "Raised Class for Mixed Material Rule". She is very largely composed of East India Class, and is in good condition.

Present Condition of the			Good		
Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	do	Breasthooks and Stenson	do	Pumps	do
Comings	do	Transoms, Pointers, and Crutches	do	Boats	do
Upper Deck Beams & Fastenings	do	Timbers of the Frame at the openings	do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	do	Ditto Ditto at other places	do	Condition, how ascertained	from deck
Planksheers	do	Keelsons	do	Sails	M. Sub & good
Sheerstrakes	do	Clamps and Shelves	do	Anchors No. of	20, 11, 11
Topsides	do	Ceiling	do	Cables	300 Y.
Wales	do	Rudder	do	Hawsers and Warps	Good &
Plank (Bottom) and Counter	do	Copper	Y.M. When put on 1871	Standing & Running Rigging	Sufficient
		Caulking of	Good		
		Bottom, Deck, & Waterways	Good		
Engine Room Skylights		Coal Bunker, Openings, Lids, &c.		Scuppers	Good
General Observations and Opinion,	and the workmanship throughout is very good. I highly respectfully recommend her as well worthy of the Committee's favourable consideration with the view to an additional year being assigned to her present class, and as eligible to be noted in the Register Book. H.T. 1873				

The Amount of Entry Fee.....£..... is received by me,  
Special.....4/4  
Certificate (if required).....  
Committee's Minute 7<sup>th</sup> Aug 1873  
Character assigned Raised to 14 A.1  
H.T. 1873 - Iron beams  
12 & 14 years material

