

REPORT of SURVEY for REPAIRS.

33296

No. in Reg. Book. No. Complete Survey held at London Date, first Survey March 16 Last Survey March 16 1872
Marque Ocean Rover Master Charles Hurton
41 Tonnage 548 built at Sunderland When built 1867-7 mo
 By whom built Thompson Owners Thompson &
 Port belonging to Sunderland Destined Voyage Cape
 If Surveyed Afloat or in Dry Dock Princes dry dock &
 Last Survey, No. 21582 Port London Classed 10. A. 1. C. F.

REPAIRS, &c.

Lifted the timbers, and nearly the whole of the ceiling below the upper turn of bilge, both sides, fore and aft, cleaned her out, and repaired the Cement. - relaid the Ceiling, stripped off the seven upper courses of the Yellow Metal Sheathing, made good the Caulking behind. Resheathed, at the same part, with Yellow Metal on felt. - put out two of the screw bolts, to see if any galvanic action had been going on, but could not discover the least signs on the iron ribs. -
 The steering gear put in order.

Present Condition of the

Decks	good	Greenails	Bolts when seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from the deck "
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors	No. of 3 12. 1 S, 2 K "
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	it was mesh when put on	part now part in "	Standing & Running Rigging	"
Engine Room Skylights		Caulking of	good			
Coat Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways				
Scuppers	good	Cargo and Main Hatchways	good		Hatches	good

General Observations and Opinion,

She is now in good condition, and the Rules Survey No. 1. having been fully complied with, I am of opinion she is entitled to remain as class'd 10. A. 1. and to be marked in the Reg. S. S. No 1.

The Amount of Entry Fee.....£ — : — : is received by me,

Special..... 2 : 2 : { 2/8/73

Certificate (if required) : :

Committee's Minute 9th September 1873

Character assigned 10 A 1

S. S. 1872

[Signature]



© 2021

Lloyd's Register Foundation

LON658-0462

Dean Rown



© 2021

Lloyd's Register
Foundation