

34761. 24.6.75
REPORT of SURVEY for REPAIRS, &c. (Rec'd 18.6.75)

No. in Reg. Book. **No.** Survey held at London Date, first Survey 15 May Last Survey 12 June 1875
on the Barque "Elizabeth Graham" Master Mordue

TONNAGE under Tonnage Deck	Built at <u>Malden</u>	When built	YEAR. <u>1869</u> MONTH. <u>2</u>
Ditto of Spar Deck, or Avoing Deck	Owners <u>Shaw Savill & Co.</u>	Port belonging to	<u>London</u>
Ditto of Poop, or Raised Qr. Dk.	Residence		
Ditto of Houses on Deck	By whom built <u>Starkes</u>	Destined Voyage	<u>Otago</u>
Ditto of Forecastle	If Surveyed Afloat or in Dry Dock	<u>In dry dock and afloat</u>	
Gross Tonnage			
Crew Space, as per Rule			
Register Tonnage, cut on Beam			
Engine Room			
Reg. Tons as St' mer, cut on Bm.			
Length of Poop <u>14.5</u> ft.	Ditto, Forecastle <u>38.8</u> ft.	Ditto, Raised Quarter Deck	Years assigned. <u>14</u> Character in Register Book. <u>A-1.</u>
Last Survey, No. <u>33267</u> Port <u>London</u> Classed <u>14</u> <u>8.73</u>			

REPAIRS, OR EXAMINATION AS PER RULE Loupe S.S. No. 1.

Lifted ceiling in hatches about equal to three strakes all fore and aft on each side at the timbers, also ceiling in hatches about equal to two strakes all fore and aft on each side below lower turn of bilge - Cement examined and repaired where required, the frames and all iron work in hold above the close ceiling and in the 'tween decks repainted; renewed the upper and lower fore topsail yards, the lower main topsail yard and the main and mizen topmasts, stripped off all the yellow metal sheathing; recaulked from keel to metal line and resheathed with yellow metal over felt.

Condition of the	Good	Good	Good
Days	Good	Treenails Balto.	Good
Deck Beams & Fastenings	Good	Breasthooks and Stemson	Good
Deck Beams & Fastenings	Good	Transoms, Pointers, and Crutches	Good
Keelsons	Good	Timbers of the Frame at the openings	Good
Clamps and Shelves	Good	Ditto Ditto at other places	Good
Ceiling	Good	Keelsons	Good
Rudder	Good	Clamps and Shelves	Good
Copper 8. mont. When put on	Good	Ceiling	Good
Caulking of	Good	Rudder	Good
Bottom, Deck, & Waterways	Good	Copper 8. mont. When put on	Good
Bottom) and Counter	Good	Caulking of	Good
Room Skylights	Good	Bottom, Deck, & Waterways	Good
Coal Bunker, Openings, Lids, &c.	Good	Bottom) and Counter	Good
Scuppers	Good	Room Skylights	Good
Cargo and Main Hatchways	Good	Coal Bunker, Openings, Lids, &c.	Good
Hatches	Good	Scuppers	Good

Observations, Opinion as to Class, &c.
She is not in good condition, but in my opinion eligible to continue as classed and marked S.S. Lon No. 1. - 75.

The Amount of Entry Fee ... £ : : received by me, 22.6.1875
Special ... £ 3 : 3 :
Certificate (if required) ... £ : 5 : 0
(Travelling Expenses, if any, £)
Committee's Minute 25th June 1875
Character assigned 14 D 1
SS 75
M 75
Surveyor to Lloyd's Register of British and Foreign Shipping.
© 2021 Lloyd's Register Foundation