

# REPORT of SURVEY for REPAIRS, &c.

35,962

No. in Reg. Book. **No.** 147 on the 19th *Inveravon* Survey held at *London* Date, first Survey *Jan 4* Last Survey *13 January 1877* Master *Cornwall*

TONNAGE under Tonnage Deck *763* Built at *London* When built *1864*  
 Ditto of Spar Deck, or Awning Deck  
 Ditto of Poop  
 Ditto of Raised Qr. Dk.  
 Ditto of Houses on Deck  
 Ditto of Forecastle  
 Gross Tonnage *835* Owners *J & P. Grant* Port belonging to *London*  
 Crew Space, as per Rule  
 Register Tonnage, cut on Beam *810* Residence  
 Engine Room  
 Reg. Tons as St'mer, cut on Bm.  
 By whom built *Mayer* Destined Voyage  
 If Surveyed Afloat or in Dry Dock *Fletcher's dock*

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft. Years assigned. Character in Register Book.  
 Classed *14* *M 9-75*  
 Last Survey, No. *35184* Port *London* *S. 9. 73.*

## REPAIRS, OR EXAMINATION AS PER RULE

*Bottom examined and found satisfactory. The iron Breasthooks below Hold Beams were all found broken. Three panting Beams have now been fitted below Hold Beams and well connected to each other and the frames by Stringer plate and angle iron. The Beams of Built Iron 6x3 1/2 and Stringer plate 15x5 1/2. The knees of the foremost Hold Beams renewed. The broken hooks removed and the lower one only repaired and replaced.*

*Surveyed with kentledge and dunnage in Hold.*

## Present Condition of the

Decks	Treenails <i>where seen good</i>	Windlass and Capstan
Waterways	Breasthooks and Stenson <i>de de</i>	Pumps
Comings	Transoms, Pointers, and Crutches <i>de de</i>	Boats <i>Good</i>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings <i>de de</i>	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places <i>de de</i>	Condition, how ascertained <i>and</i>
Planksheers	Keelsons <i>de de</i>	Sails
Sheerstrakes	Clamps and Shelves <i>de de</i>	Anchors No. of <i>complete</i>
Topsides	Ceiling <i>de de</i>	Cables
Wales	Rudder <i>de de</i>	Hawsers and Warps
Plank (Bottom) and Counter <i>where seen</i>	Copper <i>G. M.</i> When put on	Standing & Running Rigging
Engine Room Skylights	Caulking of	Cargo and Main Hatchways
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways	Hatches
Scuppers		

## General Observations, Opinion as to Class, &c.

*This vessel appears in good condition and eligible to remain as classed.*

The Amount of Entry Fee ... £ : : received by me, }  
*5/1/77* Special ... £ 3 : 3 : *26 Jan 1877* }  
 Certificate (if required) ... £ : 5 :  
 (Travelling Expenses, if any, £ )  
 Committee's Minute *21st February 1877*  
 Character assigned *14A*  
*W.D.W.*

Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2021

Lloyd's Register Foundation

LON662-0023



Imura von



© 2021

Lloyd's Register  
Foundation

ВЕБОВИ 91 2021