

# REPORT of SURVEY for REPAIRS, &c.

36 212  
Recd 19.5.77

No. in Reg. Book. **No.** Survey held at London Date, first Survey 14 April Last Survey 10 May 1877

373 on the "P. Courmahal" Master Peters

TONNAGE under Tonnage Deck 853  
 Ditto of Spar Deck, or Awning Deck  
 Ditto of Poop  
 Ditto of Raised Qr. Dk.  
 Ditto of Houses on Deck  
 Ditto of Forecastle  
 Gross Tonnage 846  
 Crew Space, as per Rule  
 Register Tonnage, cut on Beam 846  
 Engine Room  
 Reg. Tons as St'mer, cut on Bm.

Built at Bridport When built 1856  
 Owners Trails Port belonging to London  
 Residence  
 By whom built  
 If Surveyed Afloat or in Dry Dock Repet does

Length of Poop 57 ft. Ditto, Forecastle 25 ft. Ditto, Raised Quarter Deck  
 Last Survey, No. 35067 Port London

Classed 14 St 10.75  
Ent 8.9  
14.7.75

REPAIRS, OR EXAMINATION AS PER RULE

On account of damage: Yellow metal stripped off and bottom cleaned down. Two additional Breasthooks, and one pair of Greenheart pointers 26 ft 6 in length fitted diagonally across the timbers forward below Hold Beams and the lower ends connected by an Iron Hook, and all well Y. metal latted. Two pairs of Hanging Knees added to Hold Beams in fore Hold. Stern planking refastened. A few Run bolts renewed. Hauler pipes and Chocks taken out and refitted, and other smaller repairs. Caulked from Keel to gunwale. Waterways and four seams of deck B. and Re-latted over felt as before.

Now supplied: Anchor 27.2.0 Test 26.15 15<sup>th</sup> Dec 1875 } Certificate  
25.0-0 " 24.15 1<sup>st</sup> Dec 1876 } signed  
 Chain Cable 30 fms 5-47.5/10 2<sup>nd</sup> Dec 1876 } J. Hartness

Present Condition of the	Treenails	Windlass and Capstan
Decks	Breasthooks and Stenson	Pumps
Waterways	Transoms, Pointers, and Crutches	Boats
Comings	Timbers of the Frame at the openings	Masts, Yards, &c.
Upper Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	Caulking of	
Engine Room Skylights	Bottom, Deck, & Waterways	
General Observations, Opinion as to Class, &c.	Coal Bunker, Openings, Lids, &c.	Cargo and Main Hatchways
	Scuppers	Hatches

This vessel appears in good condition and eligible to remain as classed.

The Amount of Entry Fee ... £ 4 : 0 : 0 received by me, }  
22/5/77 Special ... £ 2 : 2 : 0 }  
 Certificate (if required) ... £ 5 : 0 : 0 }  
 (Travelling Expenses, if any, £ )

Committee's Minute 25th May, 1877

Character assigned

Surveyor to Lloyd's Register of British and Foreign Shipping.

© 2021 Lloyd's Register Foundation

LON662-0142