

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No.** 195 on the Ship "Newcastle" Survey held at London Date, first Survey 24 June Last Survey 9th July 1877. Master J. French

TONNAGE under Tonnage Deck 1009
Ditto of Spar Deck, or Awning Deck
Ditto of Poop
Ditto of Raised Qr. Dk.
Ditto of Houses on Deck
Ditto of Forecastle
Gross Tonnage 1137
Crew Space, as per Rule
Register Tonnage, cut on Beam 1137
Engine Room
Reg. Tons as St' mer, cut on Bm.

Built at Sunderland When built 1859
Owners Foley & Co Port belonging to London
Residence 110 Fenchurch Street E.C.
By whom built Pile Destined Voyage
If Surveyed Afloat or in Dry Dock Greens by both & Afloat

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.
Last Survey, No. 35752 Port London Conty. Lon 73-9 9-76
Classed 14 A.1.

REPAIRS, OR EXAMINATION AS PER RULE Half Time Survey &c.

Yellow metal sheathing removed, the bottom and keel examined, hold cleared and staves made, all timbers and listings cleared; Treennails and bolts driven out as per Rule; Windlasses unhung wood lining stripped off and Chain Cables ranged on deck, and the requirements of the Rules fully complied with.
Vessel recaulked from keel to gunwale also lower deck, and the bottom sheathed with yellow metal over Felb.

Present Condition of the					
Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	Turn Deck
Planksheers	"	Keelsons	"	Sails	Good
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of	3 1/2 15 2 1/2 size
Topsides	"	Ceiling	"	Cables	300 fathrs Good
Wales	"	Rudder	"	Hawsers and Warps	and
Plank (Bottom) and Counter	"	Copper Y. M. F. When put on	Now	Standing & Running Rigging	Sufficient
Engine Room Skylights	"	Caulking of	"	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	Good	Hatches	Good
General Observations, Opinion as to Class, &c.	This vessel is now in good and efficient				

Amount of Entry Fee ... £ 1 : 0 : 0 received by me, 23 July 1877
Special ... £ 4 : 4 : 5
Certificate (if required) ... £ 5 : 0 : 0
Expenses, if any, £ 0 : 0 : 0

Committee's Minute
Character assigned
24th July 1877
Surveyor to Lloyd's Register of British and Foreign Shipping.
Lloyd's Register Foundation
LON 662-0220