

and examined 300 fastenings in all.
Knee & Binding Bolts tested.

Renewed, 2 Planks in Stowage & 1 cut in the bow & bottom
on both sides & 1 Deck one Stake of Main Deck Yellow Pine.
Additional. Inner Waterway on Upper Deck on both sides
of Pitch Pine 14 inches by 12 inches well bolted through the
the side of the ship and beam ends with galvanized iron.
3 Pairs of hanging knees to lower hold beams through
bolted with yellow metal.

Caulked from keel to Gunwale Waterways
and three Stakes of Deck
Re yellow Metalled on felt to lead line

Senhouse Martindale
Wm. C. Davey