

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No.** 1366 on the BK Asshur Survey held at London Date, first Survey Nov 26 Last Survey Jan 12 1878

Master
 TONNAGE under Tonnage Deck
 Ditto of Spar Deck, or Awaiting Deck
 Ditto of Poop
 Ditto of Raised Qr. Dk.
 Ditto of Houses on Deck
 Ditto of Forecastle
 Gross Tonnage
 Crew Space, as per Rule
 Register Tonnage, cut on Beam
 Engine Room
 Reg. Tons as St'mer, cut on Bm.

Built at Aberdeen When built 1863 3
 Owners A Hector Port belonging to London
 Residence
 By whom built In this Destined Voyage
 If Surveyed Afloat or in Dry Dock In Dry Dock

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck 38 ft.
 Last Survey, No. 35495 Port London
 Character in Register Book. Classed 1041 5.75
But in 73. 7 years

REPAIRS, OR EXAMINATION AS PER RULE

At the present time placed in Dry Dock the Yellow Metal stripped off the bottom, the hold cleared and stages made inside and outside, limbers and all air courses cleared, partly scraped bright. 12 keeneails driven out at various places on both sides. C of knee and binding bolts tested. Chain cables ranged on deck & examined 270 fathoms. Windlass unruined and woodlining stripped. Renewed the keeneails from calgo to light Mark (being renewed above when continued) with stringy bark. Both knightheads & Harrosettimbers Eng Oak, one Harrosettimber Morra. Caulked from keel to load line & Yellow Metalled on felt to dottle.

Present Condition of the					
Decks	Good	Treenails	Good	Windlass and Capstan	
Waterways	"	Breasthooks and Stemson	"	Pumps	
Comings	"	Transoms, Pointers, and Crutches	"	Boats	
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	Good &
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	Inspected
Planksheers	"	Keelsons	"	Sails	where
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of 3 Bra 24 Ropes	they
Topsides	"	Ceiling	"	Cables Comd. 270 ft	condu
Wales	"	Rudder	"	Hawsers and Warps	be
Plank (Bottom) and Counter	"	Copper Metal When put on	Now	Standing & Running Rigging	seen
Engine Room Skylights	"	on felt & load line		Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	"	Caulking of		Hatches	Good
General Observations, Opinion as to Class, &c.		Bottom, Deck, & Waterways	Good		

She is now in good condition and entitled to remain as classed and Marked F.T. 1878

Surveyor to Lloyd's Register of British and Foreign Shipping.

The Amount of Entry Fee ... £ 1 : : : received by me, }
 14/1/78 Special ... £ 3 : 3 : - } 18 Jan 1878
 Certificate (if required) ... £ - : 5 : - }
 (Travelling Expenses, if any, £)
 Committee's Minute 15th January, 1878.
 Character assigned Coups 7 A
DR 4578 - Young

