

REPORT of SURVEY for REPAIRS, &c.

No. 38550

(Rec'd. 15th 10/79)

No. in Reg. Book. 1270 on the B^{re} Corea

Survey held at London

Date, first Survey 23 Sept 79 Last Survey 13th October 1879

Master Burleigh

TONNAGE under Tonnage Deck 566
Ditto of Spar Deck, or Awning Deck
Ditto of Poop
Ditto of Raised Qr. Dk.
Ditto of Houses on Deck
Ditto of Forecastle
Gross Tonnage 581
Crew Space, as per Rule
Register Tonnage, cut on Beam 581
Engine Room
Reg. Tons as St^rmer, cut on Bm.

Built at Workington When built 1859 7
Owners J. St. Mushby Port belonging to Workington
Residence
By whom built Fell Destined Voyage Hong. Kong.
If Surveyed Afloat or in Dry Dock Limekiln Dry Dock

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.
Classed 14 Years assigned. Character in Register Book.
Last Survey, No. 34350 Port London
Built. Lon. June 74 - 94rs. 4. 48

REPAIRS, OR EXAMINATION AS PER RULE in Half Time Survey -
Vessel placed in dry dock and her yellow metal sheathing stripped off. The hold cleared and proper stays made both on the inside and outside. The timbers lifted and all air courses and listrings cleared. About a dozen treenails removed for examination on each side. The timbers of frame and planking examined in air courses, listrings, timbers and treenail holes. Windlass stripped and unbung - chain cables ranged on deck and spars examined from aloft.
Repairs now done. Main mast - maintopmast and main topgallant mast renewed.
Bottom caulked from keel to metal line and resheathed with yellow metal over felt to the same height as before.

Present Condition of the					
Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	Dr	Breasthooks and Stemson	Dr	Pumps	Dr
Comings	Dr	Transoms, Pointers, and Crutches	Dr	Boats	Dr
Upper Deck Beams & Fastenings	Dr	Timbers of the Frame at the openings	Dr	Masts, Yards, &c.	Dr
Lower Deck Beams & Fastenings	Dr	Ditto Ditto at other places	Dr	Condition, how ascertained	From aloft
Planksheers	Dr	Keelsons	Dr	Sails	Good
Sheerstrakes	Dr	Clamps and Shelves	Dr	Anchors No. of	3B. 1S. 2K
Topsides	Dr	Ceiling	Dr	Cables	270 fms - Good
Wales	Dr	Rudder	Dr	Hammers and Warps	Dr
Plank (Bottom) and Counter	Dr	Copper	Full metal	Standing & Running Rigging	Dr
Engine Room Skylights		Caulking of		Cargo and Main Hatchways	Dr
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways	Good	Hatches	Dr

General Observations, Opinion as to Class, &c. She is now in a good and efficient condition and the Rules for Half Time Survey having been complied with we are of opinion that she is eligible to remain as classed and to be noted H.T. Lon. 79 in the Register Book

The Amount of Entry Fee ... £ : : : received by me, Coll.
Special ... £ 4 : 4 : - 22 Oct 79
Certificate (if required) ... £ : 5 : -
(Travelling Expenses, if any, £)

Committee's Minute 17th October, 18 79.

Character assigned Bout 9

Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2021

Lloyd's Register Foundation

LON664-0023