

39149 319149
REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. 39149 Survey held at London Date, first Survey 23rd Apr Last Survey 28th Apr 1880
on the "Palcombe" Master Rne
TONNAGE under Tonnage Deck
Ditto of Spar Deck, or Awning Deck
Ditto of Poop
Ditto of Raised Qr. Dk.
Ditto of Houses on Deck
Ditto of Forecastle
Gross Tonnage 360
Crew Space, as per Rule
Register Tonnage, cut on Beam
Engine Room
Reg. Tons as St^rmer, cut on Bm.
Built at Sunderland When built 1861
Owners Hawkey & Co Port belonging to London
Residence
By whom built Austin Destined Voyage West Indies
If Surveyed Afloat or in Dry Dock Nelson dug Dock Afloat

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.
Last Survey, No. 36228 Port London
Classed 11A 15.77
9412 yrs hat 1862.77

REPAIRS, OR EXAMINATION AS PER RULE

Yellow metal patched where necessary -
Application made by Owners for improved Classification. Survey made accordingly and first Entry Report compared with Amended Table A from which it appears that her materials do not merit more than one Year on the mixed material Rule which has already been assigned her - Her fastenings have also been examined; ceiling bolts appear from specimen drawn out to have been galvanised. Arms of knees are however fastened with plain iron. Upper deck ones found wasted & now renewed in lading knees with galv^d iron - Hold Beam knee bolts not renewed. She is therefore not fastened in accordance with 2nd clause of Sec 46 for 2 yrs for G. M. fastenings &c - and consequently not eligible for further improvement of Classification

Present Condition of the	Good	Good	Good	Good	
Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	-	Breasthooks and Stemson	-	Pumps 2 main & 2 helge	-
Comings	-	Transoms, Pointers, and Crutches	-	Boats 3 no	-
Upper Deck Beams & Fastenings	Good	Timbers of the Frame at the openings	-	Masts, Yards, &c.	-
Lower Deck Beams & Fastenings	Good	Ditto Ditto at other places	Not seen	Condition, how ascertained	Seen from Deck
Planksheers	-	Keelsons	Good	Sails	Good
Sheerstrakes	-	Clamps and Shelves	-	Anchor No. of 3 B. 15 & 2 H	-
Topsides	-	Ceiling	-	Cables	part seen Good
Wales	-	Rudder	-	Hawsers and Warps	3 no
Plank (Bottom) and Counter	Not seen	Copper 3 1/2 in When put on 1877	-	Standing & Running Rigging	-
Engine Room Skylights	-	Caulking of	-	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	-	Bottom, Deck, & Waterways	Good	Hatches	Good
Scuppers	Good				

General Observations, Opinion as to Class, &c.

She is now where seen in good condition and in my opinion may continue as classed

The Amount of Entry Fee ... £ : : : received by me, }
Special ... £ : : : 187 }
Certificate (if required) ... £ : : :
(Travelling Expenses, if any, £ : : :)

Committee's Minute

Character assigned

Tuesday, May 4th 1880
Tuesday, August 24th 80

Wm. B. Davy
Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2021

Lloyd's Register Foundation

LON664-0269