

Report of Survey for Repairs of Engines and Boilers.

No. 39853 *Lon*
 (Received at London Office, 2 12 80)
 No. in Reg. Book. 276 Survey held at London Date, first Survey Oct. 18th Last Survey Dec. 1st 1880
on the Machinery of the S.S. "Widgeon" (Number of Visits 3)
 Tonnage, Gross 788 Built at Newcastle When built 1876
 Ditto, Net 503 Owners J. G. S. N. Co. Port belonging to London
 Diameter of Cylinder 32" x 60" Engines made by Thompson & Co. When made 1876
 Length of Stroke 36" Boilers made by Ditto When made 1876
 Pressure of Steam 65 lbs. If Surveyed Afloat or in Dry Dock Afloat Years assigned 100A1
 Registered Horse Power 160 Character in Register Book
 Last Survey No. Lloyds M.C. 5.76
 Port

Particulars of Repairs and Examination According to the requirements for Special Survey No 1

Examined cylinders Slide Valves and Valve faces which were all found to be in good condition -
Crank shaft examined and found in good condition
New valves fitted to Feed pumps. Boilers examined -
Combustion Chambers, tube plates and stays in
good condition, sides of furnaces found to be
more or less pitted -

Vessel placed on gridiron sea connections found
to be in good condition, the plates at back of
the Main sections found to be much corroded
as seen through the roses, recommended that
these roses be taken off the next time the ship
is docked, & the plates properly examined
Safety Valves tested under steam to the working pressure
of 60 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The Engines & Boilers
of this ship being now in good and safe working
condition are eligible in my opinion to be marked
in the Register Book with Lloyds M.C. 11.80

Entry or Registering Fee 2/12 £ 1 : 10 :
 Survey Fee ... £ 3 : 3 : received by me, C. E. R.
 Certificate (if required) ... £ 5 : 2/3 1881

(Travelling Expenses, if any, £)

Committee's Minute

Friday, December 3rd. 1880.

Assigned

Lieut. E. W. Wilson
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register
 Foundation

LON664-0528

It is submitted that the
vessel is eligible
to have the notification

Lloyd's M.C. 12. 80

recorded in the
Register Book

M

2/12/80



© 2021

Lloyd's Register
Foundation