

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office,)

No.

No. in Reg. Book.

Survey held at *London*

Date, first Survey *Feb. 4th* Last Survey *Feb. 15th* 188*1*.

7 on the Machinery of the *S. S. "Haveteur"*

(Number of Visits *5*)

Tonnage, Gross *1254*

Built at *Hartlepool*

When built *1876*

Ditto, Net *803*

Owners *Steel Young & Co.*

Port belonging to *London*

Diameter of Cylinder *28" + 53"*

Engines made by *Richardson & Sons*

When made *1876*

Length of Stroke *33"*

Boilers made by *Ditto*

When made *1876*

Pressure of Steam *65 lbs.*

If Surveyed Afloat or in Dry Dock *Dry Dock & Afloat*

Classed

Years assigned.

Character in Register Book.

90A1

Registered Horse Power *110*

Last Survey No.

Port

Lloyds M.C. 12.76.

Particulars of Repairs and Examination According to the requirements for Special Survey No 1.

Examined High Pressure cylinder Slide Valve & Valve Face which were found to be in good condition. Low Pressure Slide Valve & face in good condition.

Examined Crank shaft which was found in good condition. Galleys in Thrust Bearing found to be very slack, these have been lined up.

Air & Circulating pumps examined & found to be in good condition. Feed & Bilge pumps & valves in good condition. Boiler examined internally & externally & found to be in good condition there being no patches on any part.

Examined Low pressure cylinder which was found to be in good condition. Donkey Boiler examined the edges of plate round mud holes, found to be much corroded, rivetted plates have been fitted over these parts & the covers fitted to them, the rest of the boiler in fairly good condition. Safety Valves in good condition. Spring Safety Valves tested under steam to the working pressure of 65 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The Engines & Boilers of this ship being now in good & safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with Lloyd's M.C. 2.81.

Entry or Registering Fee ... £ *1 : 0 : 0*

Survey Fee *2.2.81* ... £ *4 : 4 : 0*

Certificate (if required) ... £ *2 : 6 : 26/2*

(Travelling Expenses, if any, £)

received by me,

26/2/1881

C. E. Bromeyer & Co.

Geo. E. Merriam
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

22/2/81

188

Assigned

Lloyd's M.C. 2.81



Lloyd's Register Foundation

LON 665-0158

It is submitted that this
vessel is eligible to
have the notification
Lloyd's M.C. 2 &
recorded
M
22/2/81



© 2021

Lloyd's Register
Foundation