

100 40132  
Report of Survey for Repairs of Engines and Boilers.

No. in Survey held at London Date, first Survey Jan 3<sup>rd</sup> Last Survey Jan 20<sup>th</sup> 1881  
g. Book. 401 on the Machinery of the S. S. John Johnasson (Number of Visits 1)  
Tuesdays February 8th. 81.  
Tonnage, Gross 554 Built at Newcastle When built 1870  
Ditto, Net 348 Owners London & Stamp Port belonging to London  
Diameter of Cylinder 36" Engines made by N & Marine Co. When made 1870  
Length of Stroke 30" Boilers made by D<sup>o</sup> When made 1880  
Pressure of Steam 45 lbs. If Surveyed Afloat or in Dry Dock Afloat  
Registered Horse Power 80 Classified Years assigned. 3-80 Character in Register Book. A 1  
Last Survey No. 3441 Port Aberdeen B.V.M.S. 1.80

Particulars of Repairs and Examination Of Boiler, to fit new Furnaces  
Crowns.

Tubes drawn from middle tube plate, the tube plate taken out in order to remove damaged crown plates of furnaces. Examined the new plates before they were fitted in, materials & workmanship found to be good. Examined combustion chambers plates & stays found to be in good condition the new crown plates fitted and all other parts refitted in an efficient manner.

General Observations, Opinion, and Recommendation:— The Boiler of this vessel being now in good & safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with BS 1.81 & M.S. 1.80.

Entry or Registering Fee ... £ 3/3/81 received by me  
Survey Fee ... £ 1/1/81  
Certificate (if required) ... £ 188  
(Travelling Expenses, if any, £ )

Committee's Minute Friday, March 4th, 1881.  
Assigned M.S. 1.80  
D.W. B.S. 1.81  
Lloyd's Register Foundation  
LN666-0209



It is submitted that this vessel  
is eligible to have the  
notification B.S. 1-81  
& M.S. 1-80 recorded

Am  
7/2/80



© 2021

Lloyd's Register  
Foundation