

Report of Survey for Repairs of Engines and Boilers.

No.

(Received at London Office,

No. in Reg. Book. Survey held at London

Date, first Survey Feb. 23rd Last Survey March 7th 1881.

285 on the Machinery of the S.S. "Agnes & Louisa"

(Number of Visits 6)

Tonnage, Gross 703

Built at Hartlepool

When built 1871

Ditto, Net 436

Owners S. Clarke & Co.

Port belonging to London

Diameter of Cylinder 25" x 48"

Engines made by Black Hawthorn & Co.

When made 1871

Length of Stroke 30"

Boilers made by Ditto

When made 1871

Pressure of Steam 55 lbs.

If Surveyed Afloat or in Dry Dock Dry dock & Afloat

Classed

Years assigned.

Character in Register Book.

90A1

Registered Horse Power 90

Last Survey No.

Port

Lloyds M.C. 4.80.

Particulars of Repairs and Examination For Annual Survey and Condition of Boiler. Tessel placed in Dry dock

Examined sea connections & propeller which were found to be in good condition. Boiler examined, the shell, furnaces & tube plates in moderately good condition. Combustion chambers found to have a number of patches & in places found to be very thin, these have been repaired with bolted patches. Reduced weights on Safety Valves to lift at 55 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The Boiler is now in good & safe working condition and eligible in my opinion to have the certification B.S. 3.81 recorded subject to the boiler being again examined within six months from this date on account of the condition of combustion chamber.

Entry or Registering Fee ... £ 0 : 0 : 0

Survey Fee ... £ 2 : 2 : 0 received by me,

Certificate (if required) ... £ 2 : 6 : 0 22/3/1881

(Travelling Expenses, if any, £)

Committee's Minute

Friday, March, 15th. 1881.

Assigned

B. S. 3.81

Geo. E. Wilson
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Lloyd's Register Foundation

LON665-0267

It is submitted that this vessel
is eligible to have the
notification BS. 3.81
recorded subject to the
Bridle being again
examined in 6 months

pm

11/3/81



© 2021

Lloyd's Register
Foundation