

SUMMER REPAIRS, REPORT of SURVEY for REPAIRS, &c.

(Received at London Office, 18 5 81)

No. 294 on the SS Thornbrough Master Watson
 No. in Survey held at London Date, first Survey May 9th Last Survey May 1881
 Reg. Book. 629 Built at Newcastle When built 1876 YEAR. MONTH. 8
 Owners J Fenwick & Son Port belonging to London
 Residence Palmer Destined Voyage Tyre
 If Surveyed Afloat or in Dry Dock Pontoon Victoria Dock
 (State Name of Dock)
 Length of Poop 789 ft. Ditto, Forecastle 463 ft. Ditto, Raised Quarter Deck 90 ft. Years assigned. 2-80 Character in Register Book. SS Lon M-80
 Last Survey, No. 75792 Port hwc
 REPAIRS, OR EXAMINATION AS PER RULE
 Cause of Repairs to be clearly stated.

At present owing to damage (Collision)
 Repairs Port Bow 2 plates being injured have
 had 2 doubling plates put on the outside and well
 rivetted, 3 broken Main Frames & 1 Reverse Frame
 have been strengthened with plates and angle iron
 and well rivetted. Top Gallant Forecastle Deck
 caulked with other small repairs. Bottom coated.

Present Condition of the	Good	Treenails	Rivets	Good	Windlass and Capstan	Good
Decks	Good	Breasthooks and Stemson	Good	Pumps	Good	
Waterways	Good	Transoms, Pointers, and Crutches	Good	Boats	Good	
Comings	Good	Timbers of the Frame at the openings	Good	Masts, Yards, &c.	Good	
Upper Deck Beams & Fastenings	Good	Ditto Ditto at other places	Good	Condition, how ascertained	From Hk	
Lower Deck Beams & Fastenings	Good	Keelsons	Good	Sails	Good	
Planksheers	Good	Clamps and Shelves	Good	Anchors No. of 3 Bcs. Hk & Ridges	Good	
Sheerstrakes	Good	Ceiling	Good	Cables <u>Paston Hk</u>	Good	
Topsides	Good	Rudder	Good	Hawsers and Warps	Good	
Wales	Good	Copper <u>Grated</u> When put on <u>New</u>	Good	Standing & Running Rigging	Good	
Plank (Bottom) and Counter	Good	Caulking of Bottom, Deck, & Waterways	Good	Cargo and Main Hatchways	Good	Hatches
Engine Room Skylights	Good	Coal Bunker, Openings, Lids, &c.	Good	Scuppers	Good	
General Observations, Opinion as to Class, &c.	<p style="text-align: center;">She is now in an efficient state and eligible to remain as classed.</p>					

Damage Fee £2-2-0

Senhouse Martindale

The Amount of Entry Fee ... £ 1 : 1 : 0 received by me, }
 Special ... £ 1 : 1 : 0 1881

Certificate (if required) to be sent as per margin... £ : :

(Travelling Expenses, if any, £)

Committee's Minute

Character assigned

Tues day, May, 24th 1881.

Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2021

Lloyd's Register Foundation

If a Steam Ship, state if a Report is also sent on the Machinery

Insert Character precisely as in Register Book.