

# Report of Survey for Repairs of Engines and Boilers.

No.

(Received at London Office, \_\_\_\_\_)

No. in Reg. Book. Survey held at London

Date, first Survey Aug 12<sup>th</sup> Last Survey See Cardiff Report No 204 1881

on the Machinery of the S. S. "Viceroy"

(Number of Visits 9 Year 1881)

Tonnage, Gross 2463

Built at London

When built 1871

Ditto, Net 1864

Owners R. & H. Green

Port belonging to London

Diameter of Cylinder 38" & 66"

Engines made by Ravenhill, Hodgen, & Co.

When made 1871

Length of Stroke 39"

Boilers made by Ditto

When made 1871

Pressure of Steam 60 lbs.

If Surveyed Afloat or in Dry Dock Loxley's

Years assigned, 100A1 Character in Register Book.

Registered Horse Power 240

Classed 100A1

Last Survey No. \_\_\_\_\_

Port \_\_\_\_\_

B.M.S. 1.80

## Particulars of Repairs and Examination For Annual Survey

(State cause of Repairs.)

Vessel placed in dry dock sea connections examined & found to be in good condition. Propeller disconnected the tail shaft drawn in for examination found to be in good condition & a new four bladed solid propeller fitted. High pressure piston turned up in lath, a new neck bush fitted & gland rebushed. Machinery generally overhauled. Both cylinders & slides examined and found in good condition. Crank shaft examined and re lined up, new eccentric to forward engine and eccentric strap rebushed. Main & Donkey Boilers examined, four patches fitted to the Donkey Boiler furnace, Crown plate drilled in several places and found in good condition. Main boiler found in fairly good condition. Safety valves tested at Cardiff see attached report (no 204)

General Observations, Opinion, and Recommendation:— In our opinion the machinery of this vessel is now eligible to have the notification B.M.S. 11.81 recorded subject to the Boilers being resurveyed in 12 months as per rule.

Entry or Registering Fee... £ — : — : —

Survey Fee (per Section 28) ... £ 2 : 2 : 0

Certificate (if required) ... £ : 5 : 1

(Travelling Expenses, if any, £ 1)

received by me, A.B.

1881

James J. Milton

Geo. C. Merriamson

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute \_\_\_\_\_

Friday, December, 2nd, 1881.

Assigned B.M.S. 11.81

Subject to be

Lloyd's Register Foundation

LON666-0163