

Report of Survey for Repairs of Engines and Boilers.

No. Lon 40590
(Received at London Tuesday, July, 12th 1881)
No. in Reg. Book. Survey held at London Date, first Survey July 1st Last Survey July 4th 1881
653 on the Machinery of the S.S. London (Number of Visits 2)
Tonnage, Gross 1325 Built at Newcastle When built 1862
Ditto, Net 831 Owners J. Hall & Co. Port belonging to London
Diameter of Cylinder 43" Engines made by R & N. Hawthorn When made 1862
Length of Stroke 33" Boilers made by _____ When made _____
Pressure of Steam 40 lbs. If Surveyed Afloat or in Dry Dock Limehouse DK & Afloat Classified 100A1
Registered Horse Power 120 (State name of Dock.)
Last Survey No. _____ Port _____

Particulars of Repairs and Examination For Annual Survey
(State cause of Repairs.)

Vessel placed in dry dock sea connections examined & found to be in good condition. Propeller and its connections found to be sound. Tail shaft down 1/8" in Stern Bush. Boilers examined the furnaces & combustion chambers found in good condition one or two patches at sides in wake of bridges. Shells of Boilers in fairly good condition Stays in good condition. The double angle irons at ends of boilers in steam space, somewhat corroded. Safety valves examined found to be in good condition & properly loaded to the working pressure of 40 lbs per sq. in. - Crank shaft examined & found to be in good condition

General Observations, Opinion, and Recommendation:— The Boilers being now in good and safe working condition renders the vessel eligible in my opinion to remain as classed than the notification B.S. 7. 81 recorded provided that the boilers are again surveyed in 12 months as per rule.

Entry or Registering Fee... £ " : " : "
Survey Fee (per Section 28) 4/7/81 £ 2 : 2 : } received by me, J. J.
Certificate (if required) ... £ - : - : } 16 July 1881
(Travelling Expenses, if any, £ _____)

Committee's Minute Friday, July, 15th 1881. Assigned _____
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



It is submitted that this vessel
is eligible to have the
notification BS 7.81
recorded subject to the
Boreas being resurveyed
in 12 months as per
rule

Mr

12/7/81



© 2021

Lloyd's Register
Foundation