

REPORT of SURVEY for REPAIRS, &c.

40493

No. 672 on the Iron S. "Grecian" Master Larance
 No. in Survey held at London Date, first Survey 30th July Last Survey 7th Sept^r 1881
 Reg. Book. 1197 Built at Greenock When built 1868 YEAR. MONTH.
 Ditto of Spar Deck, or Av'ing Deck Owners W. Orr Port belonging to Greenock
 Ditto of Poop Residence
 Ditto of Raised Or. Dk. By whom built Scott Destined Voyage Sydney
 Ditto of Houses on Deck If Surveyed Afloat or in Dry Dock Carter's dry Dock Afloat
 Ditto of Forecasts (State Name of Dock)
 Gross Tonnage 1332
 Crew Space, as per Rule
 Register Tonnage, cut on Beam 1272
 Engine Room
 Reg. Tons as St^rmer, cut on Bm.

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.
 Last Survey, No. 27725 Port Iron Classed A 1 9.80
 REPAIRS, OR EXAMINATION AS PER RULE No 3 S.S. Dunk no 2.77
 Cause of Repairs to be clearly stated.

*All the close ceiling lifted fore and aft on both sides
 oxidation removed from floors and frames examined and
 found good, plating not drilled, being found good.
 ceiling relaid - bottom painted, spars examined.
 Cables caulked out
 new wooden mast
 new upper topsail yard*

Present Condition of the	Good	Greenails	Rivets	Good	Windlass and Capstan	Good
Decks	—	—	—	—	—	—
Waterways	—	Breasthooks and Stems	—	—	Pumps, 2 hand 2 helix	—
Comings	—	Transoms, Pointers, and Crutches	—	—	Boats 4 no	—
Upper Deck Beams & Fastenings	—	Timbers of the Frame at the openings	—	—	Masts, Yards, &c.	—
Lower Deck Beams & Fastenings	—	Ditto Ditto at other places	—	—	Condition, how ascertained by Exam ⁿ	—
Planksheers	—	Keelsons	—	—	Sails	Good
Sheerstrakes	—	Clamps and Shelves	—	—	Anchors No. of 3 B. 18 & 2 1/2	—
Topsides	—	Ceiling	—	—	Cables 300 fms	Good
Wales	—	Rudder	—	—	Hawsers and Warps 3 no	—
Plank (Bottom) and Counter	—	Copper (on V.M.) Cement When put on 68	—	—	Standing & Running Rigging	—
Engine Room Skylights	—	Caulking of Bottom, Deck, & Waterways	Good	—	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	—	Scuppers	Good	—	Hatches	Good

General Observations, Opinion as to Class, &c.
*She is now in good condition eligible in
 our opinion to continue as classed and marked
 S S Lon no 3. 81*

The Amount of Entry Fee ... £ : : : received by me, }
 16/9/81 Special ... £ 5 : 5 : - 19/9/1881 }
 Certificate (if required) } £ : 5 : -
 to be sent as per margin... }

Wm. C. Davy
Surveyor to Lloyd's Register of British and Foreign Shipping.
Charles Edwards

Committee's Minute Friday, September, 16th 1881
 Character assigned A 1



Form No. 2 for Repairs. - 1,000-19/81. (The Surveyors are requested not to write on or below the space for Committee's Minutes.) (If a Steam Ship, state if a Report is also sent on the Machinery.) (Insert Character precisely as in Register Book.)