

40961

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office, 6. 12. 81)

No.

No. in Survey held at London

Date, first Survey 30 Sept. Last Survey 30 Nov 1881

1455 on the Machinery of the S. J. Avera

(Number of Visits 6)

Tonnage, Gross 728

Built at Lunderland.

When built 1873

Ditto, Net 459

Owners W Thorton

Port belonging to Uddvalla

Diameter of Cylinder 24 & 48

Engines made by Onseburn Eng Wks

When made 1873

Length of Stroke 33"

Boilers made by "

When made 1873

Pressure of Steam 50

If Surveyed Afloat or in Dry Dock Afloat in Commercial Dk. Classified 90 A1

Years assigned, Character in Register Book.

Registered Horse Power 95

(State name of Dock.)

S. S. Nov-48 9.81.

Last Survey No. 40915

Port Lon

B & M S. 9.80

Particulars of Repairs and Examination Annual. (Age of boilers)

(State cause of Repairs.)

Examined boiler and found it to be in a good condition. The donkey stop valve was leaking and had filled the super-heater, which could not be examined till a month later and was then found to be in good condition.

The safety valves (lever) are loaded to 65 lbs per square that being the original working pressure. The recorded working pressure had been reduced when the boilers were tested to 100 & about 12 months ago. For particulars see letter by C A Miller 20/11/81.

[Large blue scribble]

General Observations, Opinion, and Recommendation:— As far as seen the boiler appears to be in a safe working condition for a pressure of 65 & and is in my opinion eligible to remain as classed and to have B.S. 11.81. and 65 lbs instead of 50 lbs recorded in the Register Book.

Entry or Registering Fee... £ " : " : "
Survey Fee (per Section 28) ... £ 3 : 3 : - received by me, C. A. Miller
Certificate (if required) ... £ : : 15/11/1881
(Travelling Expenses, if any, £)

C. A. Miller
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute Tuesday, December, 13th, 1881.

Assigned B.S. 11.81
Surveyor



LON667-0112

(State if Report is also sent on the Hull of the Ship...)

(The Surveyors are requested not to write on or below the space for Committee's Minute.)

(Insert Character precisely as in the Register Book.)

It is submitted that this vessel
is eligible to have the notifi-
cation BS 11. 81 recorded,
subject to the boiler being
again SD in 12 months
as per rule

M J B W
5/12/81

