

REPORT of SURVEY for REPAIRS, &c.

No. 40978  
No. in Survey held at London Date, first Survey Nov-22 Last Survey Dec-5 1881  
Reg. Book. 319 on the Screw Steamer "Virgo" Master J. H. Seaton  
Official Number 63694 Tonnage under Tonnage Deck 818  
Ditto of Spar Deck or Awaiting Deck  
Ditto of Poop  
Ditto of Raised Qr. Dk.  
Ditto of Houses on Deck  
Ditto of Forecastle  
Gross Tonnage 1016  
Crew Space, as per Rule  
Register Tonnage, cut of Beam  
Engine Room  
Reg. Tons as S'mer, cut on Bm. 585  
Built at Dundee When built 1870 - 11  
Owners General Steam Navigation Co Port belonging to London  
Residence  
By whom built Gourlay Brothers Destined Voyage Scotland  
If Surveyed Afloat or in Dry Dock G.S.N. Co Dry Dock, Deptford & Afloat  
(Stat Name of Dock)  
Length of Poop 74 ft. Ditto, Forecastle 61 ft. Ditto, Raised Quarter Deck ft.  
Classed 100 A 1  
Last Survey, No. 40764 Port London S. S. Law 2-80 11, 80  
REPAIRS, OR EXAMINATION AS PER RULE  
Cause of Repairs to be clearly stated.

The bottom examined and recoated with Black Varnish. Renewed 4 planks in the deck on port side and 3 on starboard side abreast of galley & deck house, with Dantzic Red Pine, - part of twelve strakes of ceiling under fore hatch in flat & bilges, renewed with American Elm and Spruce. The main deck all fore and aft also the fore & after tween decks, recaulked; part of the wood planking over top of tunnel in way of hatchway renewed. The ceiling in after hold lifted for examination of the cement and cleaning. Two new plates in the rudder, and wrought iron straps or clamps fitted outside the plating in way of a break in the after part of the rudder frame, and the back frame rivetted together with the parts in way of new plates. The Chain Cables ranged and examined.

Present Condition of the.		Broom & Harfield's	
Decks	Repaired	Freemasts	Windlass and Capstan
Waterways	Good	Rivets	Good
Comings	"	Breasthooks and Stemson	"
Upper Deck Beams & Fastenings	"	Transoms, Pointers, and Crutches	"
Lower Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"
Planksheers	"	Ditto Ditto at other places	"
Sheerstrakes	"	Keelsons	"
Topsides	"	Clamps and Shelves	"
Wales	"	Ceiling	"
Plating (Bottom) and Counter	"	Rudder	"
Engine Room Skylights	Good	Copper (or Y.M.)	Counted When put on 1870
Coal Bunker, Openings, Lids, &c.	Good	Caulking of	Good
General Observations, Opinion as to Class, &c.		Bottom, Deck, & Waterways	Good
		Scuppers	Good
		Cargo and Main Hatchways	Good
		Hatches	Good

This vessel is now in good and efficient condition and eligible to remain as classed.

The Amount of Entry Fee ... £ 2 : 2 : received by me, 27/12/81

Certificate (if required) to be sent as per margin... £ 5 : -

Surveyor to Lloyd's Register of British and Foreign Shipping.

(Travelling Expenses, if any, £ )  
Committee's Minute

Friday, December, 16th. 1881

or assigned

100 A 1  
Subject to the Bank of England  
ROBT. EDMD. TAYLOR & SON, Commercial Steam Printers, 15 Old Street, Goswell Road, London.  
LON 667-0139

Sub Owners  
23/12/81

Lloyd's Register  
Foundation