

41097

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Received at London Office, 21. 1. 82.)

No. in Reg. Book. Survey held at London Date, first Survey Jan. 11th Last Survey Jan. 17th 1882

379 on the Machinery of the S. S. "Berrington" (Number of Visits 3)

Tonnage, Gross <u>794</u>	Built at <u>Newcastle</u>	When built <u>1865</u>
Ditto, Net <u>508</u>	Owners <u>J. Fenwick & Sons</u>	Port belonging to <u>Sunderland</u>
Diameter of Cylinder <u>25" & 48"</u>	Engines made by <u>Compd. Palmers Co.</u>	When made <u>1876</u>
Length of Stroke <u>30"</u>	Boilers made by <u>Ditto</u>	When made <u>1876</u>
Pressure of Steam <u>75 lbs.</u>	If Surveyed Afloat or in Dry Dock <u>Afloat & Afloat</u>	Classed <u>80A1</u>
Registered Horse Power <u>99</u>	(State name of Dock.)	

Last Survey No. _____ Port Lloyds M.C. 4.79

Particulars of Repairs and Examination According to the requirements for Special Survey No 2.

Vessel placed on Pontoon sea connections examined & found to be in good condition, the propeller sound & tail shaft down $\frac{1}{4}$ " in Stern Bush.

Examined cylinders slides & Valve faces, found in good condition. Crank shaft in good condition. Air circulating Feed & Bilge pumps & valves in good condition.

Boilers examined found to be in good condition, a few seams only having to be caulked. Safety Valves examined & found to be in good condition.

Dontrey boiler examined a new uptake has been fitted, furnace & shell in moderately good condition.

Safety Valve examined a new spindle has been fitted (iron) loaded to 40 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with Lloyds M.C. 1. 82. provided that the boilers are again submitted for survey in 12 months as per rule.

Entry or Registering Fee... £ 1 : - : -
Survey Fee (per Section 28) ... £ 3 : 3 : -
Certificate (if required) ... £ - : - : -
(Travelling Expenses, if any, £ -)

received by me, J. M. J.
27.1. 1882

Geo. C. Thompson
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute _____ Tuesday, January, 24th. 1882.

Assigned _____



LON667-0290

It is submitted that this vessel
is eligible to have the
notification Lloyd's MC 1.82
recorded subject to the
Bordas being reassured
in 12 months as per
rule

M 20/1/82



© 2021

Lloyd's Register
Foundation