

Report of Survey for Repairs of Engines and Boilers.

No. *205* on the Machinery of the *Steam Ship Despatch* (Number of Visits *3*)
 No. in Reg. Book. *London* Date, first Survey *10th Mar* Last Survey *16th Mar* 188 *2*
 Tonnage, Gross *734* Built at *Newcastle* When built *1863*
 Ditto, Net *465* Owners *J. Fenwick & Sons* Port belonging to *London*
 Diameter of Cylinder *25" & 48"* Engines *comp^d by Die dock engine Co* When *1875*
 Length of Stroke *30"* Boilers made by *do do* When made *1875*
 Pressure of Steam *70 lbs* If Surveyed Afloat or in Dry Dock *Die dock Putoon* Years assigned. *1* Character in Register Book. *A1*
 Registered Horse Power *90* (State name of Dock.)
 Last Survey No. *Lloyds M.C. 3.78* Port *Lloyds M.C. 3.78*

Particulars of Repairs and Examination *For Special Survey No 1.*
 (State cause of Repairs.)
Exam^d Sea cocks & connections, also bolts through Ships Shell & find them in good condition
Exam^d Stern bush which is $\frac{5}{16}$ " down. propeller and its connections found to be sound
Exam^d Air & Circulating & Bilge pumps and found them in good condition
Exam^d Condenser & found tubes & ferrules good
No bilge injection valve fitted upon these engines
Recommended valve be fitted & suction pipe fitted
Exam^d Crank Shaft & find all bearing & crank pins in good condition
Exam^d both cylinders & both slide valves & find them in good condition.
Exam^d both boilers also Superheater found several stays in Superheater badly wasted recommended that they be taken out & new stays fitted in other parts of boilers in good condition
Exam^d Safety valves & find them in good condition and tested to lift at 70 lbs □

General Observations, Opinion, and Recommendation:— *The machinery being now in good & safe working condition renders the vessel eligible in our opinion to be marked in the register book with Lloyds M.C. 3.82 provided the boilers are again exam^d within twelve months as per rule*

Entry or Registering Fee. *£ 1 : - : -*
 Survey Fee (per Section 28) ... *£ 2 : 2 : -*
 Certificate (if required) ... *£ : : -*
 (Travelling Expenses, if any, £ *---*)
 received by me, *Rich^d Hirst* 3rd Apr 1882

Committee's Minute *Tuesday, April, 4th 1882.*
 Assigned *Lloyd M.C. 3.82*
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
 Lloyd's Register Foundation
 LON607-0501

It is submitted that this vessel is
eligible to have the notifica-
tion Lloyd MC. 3. 82
recorded subject to the
vessel being resurveyed
in 12 months as per rule

M
1/4/82



© 2021

Lloyd's Register
Foundation