

REPORT of SURVEY for REPAIRS, &c.

41324

(Received at London Office, 3/4/82)

No. 1492 on the Bk "Rheinland" late "Lumberland" Date, first Survey 9th Mar Last Survey 1st April 1882
 Reg. Book. 1492 Master A. Moekius 14 Visits

TONNAGE under Tonnage Deck 810 Built at Sunderland When built 1856
 Ditto of Spar Deck, or Arming Deck
 Ditto of Poop
 Ditto of Raised Or. Dk.
 Ditto of Houses on Deck
 Gross Tonnage 891 Owners O. Moekius Port belonging to Hamburg
 Crew Spaces as per Rule
 Register Tonnage, cut on Beam 861 Residence
 By whom built
 Engine Room
 Reg. Tons as St^rmer, cut on Bm.
 If Surveyed Afloat or in Dry Dock Afloat Millwall Dk (State Name of Dock)
 Destined Voyage Vera Cruz via Cardiff

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft. Years assigned 13 A 1 Red
 Last Survey, No. 1454 Port Mus Classed S.S. Ply 78.9 yrs
 REPAIRS, OR EXAMINATION AS PER RULE
 Cause of Repairs to be clearly stated.

A piece scuffed to head of Stabd Knight head. one house timber on each side renewed from house pipe upwards with Baltic Oak one plank of bores Port side new Baltic Oak, 10 new G. M. bolts additional. next to throat bolts of Stold Beam hanging knees introduced. 19 iron staple lodging knees on each side to Stold Beam removed. G. M. beam filling introduced and the knees refitted and G. M. bolted. New Fore mast Pitch Pine. Fore lower topsail Yard and main Top gallant Yard

Present Condition of the					
Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	---	Breasthooks and Stenson	---	Pumps	2 No
Comings	---	Transoms, Pointers, and Crutches	---	Boats	4 No
Upper Deck Beams & Fastenings	---	Timbers of the Frame at the openings	---	Masts, Yards, &c.	---
Lower Deck Beams & Fastenings	---	Ditto Ditto at other places	Not seen	Condition, how ascertained	
Planksheers	---	Keelsons		Sails	Good
Sheerstrakes	---	Clamps and Shelves	where seen of clear ballast good	Anchors	No. of 3 B. 15 & 2k
Topsides	---	Ceiling	Good	Cables	part seen Good
Wales	---	Rudder	Good	Hawsers and Warps	3 No
Plank (Bottom) and Counter	Not seen	Copper (or Y.M.) on it	When put on 8/80	Standing & Running Rigging	---
Engine Room Skylights	---	Caulking of Bottom, Deck, & Waterways	Good	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	---	Scuppers	Good	Hatches	Good
General Observations, Opinion as to Class, &c.					

General Observations, Opinion as to Class, &c.

She is now in good condition as far as seen eligible to continue as Classed

Will. C. Dacey

Surveyor to Lloyd's Register of British and Foreign Shipping.

The Amount of Entry Fee ... £ 1 : - : - received by me, 478
 Special ... £ 2 : 2 : - 8th April 1882

Certificate (if required) to be sent as per margin... £ : 5 : -

(Travelling Expenses, if any, £)

Committee's Minute

Tuesday, April, 4th 1882.

Character assigned

[Signature]



© 2021

Lloyd's Register Foundation

LON 668-0005