

Report of Survey for Repairs of Engines and Boilers.

X-41492

(Received at London Office, ...)

Survey held at London & Leamth Date, first Survey 20th March Last Survey 10th May 1882

on the Machinery of the Screw Steamer Wmbleton (Number of Visits ...)

Gross <u>1474</u>	Built at <u>Stockton</u>	When built <u>1872</u>
Net <u>957</u>	Owners <u>Harris & Dixon</u>	Port belonging to <u>London</u>
of Cylinder <u>30 1/2 x 61</u>	Engines made by <u>Blair & Co</u>	When made <u>1872</u>
Stroke <u>39"</u>	Boilers made by <u>Do</u>	When made <u>1872</u>
of Steam <u>65# per sq. inch</u>	If Surveyed Afloat or in Dry Dock <u>Immelin Dock</u>	Classed <u>100 A 1</u>
Horse Power <u>140</u>	(State name of Dock.)	Years assigned <u>12.79</u>
Survey No. <u>*688</u>	Port <u>Ant</u>	Character in Register Book. <u>12.79</u>

Particulars of Repairs and Examination of engines and boilers in accordance with the requirements of the Rules for S.S. No. 3

Sea cocks & propeller fastenings found satisfactory

In mtr shaft, cylinders, slide valves & pump thoroughly overhauled & found in good condition

Main boilers examined, lower portions of combustion chambers & front bottom plates renewed

New Donkey boiler fitted which has been constructed in accordance with the Rules by Clarke Chapman & Gurney for a working pressure of 80 lbs. per square inch

Safety valves (Leas) of Mainboilers seen under steam, blowing off at 65# per sq. inch

Spring Safety valve of donkey boiler blowing off at 64# per sq. inch.

Mr Keydell's Report - H. 28

any
Lee
expenses
adit

al Observations, Opinion, and Recommendation:— The machinery of this vessel now in good order and safe working condition and eligible in opinion to have the notification Lloyd's M.B. 5.42 recorded next to the Main boilers being renewed in 12 months as Rule

Registering Fee, 18/1/83 £ 1 : - : -

ee (per Section 28) ... £ 2 : 2 : - received by me, J. H. E. Keydell

ificate (if required) ... £ 2 : 26 : 1 1883 } David F. Jones

sent as per margin.

expenses, if any, £ - 2/6

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

London

Committee's Minute Tuesday, 23rd May, 1882.

Assigned Lloyd's M.B. 5.42

J. H. E. Keydell

Lloyd's Register Foundation

LON 688-0194