

# Report of Survey for Repairs of Engines and Boilers.

No. 729 on the Machinery of the S. S. "Lord of the Isles" (Received at London Office, 19/6/88)  
No. in Reg. Book. 729 Survey held at LONDON Date, first Survey 8 May Last Survey 30 June 1882  
Tonnage, Gross 2484 Built at Glasgow When built 1870  
Ditto, Net 1586 Owners Shaw Bushby & Co Port belonging to London  
Diameter of Cylinder 44 & 76 Engines made by C. D. Holmes & Co When made 1878  
Length of Stroke 48 Boilers made by W. & A. Mitchell & Co When made 1878  
Pressure of Steam 75 If Surveyed Afloat or in Dry Dock London Dock & Millwall Dock Years assigned 100 A 1  
Registered Horse Power 350 (State name of Dock.) 9 West India St. Character in Register Book. 11 80  
Last Survey No. Lloyds M.C. 6.78. Port LONDON

Particulars of Repairs and Examination Special Survey No 3 and Damage  
(State cause of Repairs.)  
Examined Leacocks & connections & found them in good condition

Two of the propeller blades had been broken & the boss split. A new boss & two new blades have been fitted. New Lignum vitae has been fitted.

Examined the boilers & superheater & found them in good condition. The donkey boiler was found in a good condition.

Examined Safety valves, slide valves, cylinders & pistons, pump & crankshaft, funnel & tail shaft & found them in good condition. A new piston had been fitted to the high pressure cylinder.

The drain pipes from the Superheater were led below the water level. Holes have now been cut into them above the water level.

The Safety valves were found to blow off at 75 lbs

General Observations, Opinion, and Recommendation:— The machinery of this vessel appears to be in a safe working condition and eligible in my opinion to have the notification Lloyds M.C. 6.82 recorded in the Register Books.

Entry or Registering Fee... £ 1 : 10 :  
(per Section 27.)

Survey Fee (per Section 28) ... £ 4 : 4 :  
Certificate (if required) ... £ 5 : 5 :  
to be sent as per margin.

(Travelling Expenses, if any, £         )

Committee's Minute

Assigned Lloyd's

received by me, CD

17/6/88 1882

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Friday, 10th June, 1882

Lloyd's Register  
Foundation

LON668-0306



It is submitted that this vessel  
is eligible to have the warfare  
story as m. b. 6. 82. recorded

D.G.

5/6/82.



© 2021

Lloyd's Register  
Foundation