

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Received at London Office, 1. 7. 82.)
 No. in Reg. Book. Survey held at London Date, first Survey May 10th Last Survey June 16th 1882.
625 on the Machinery of the S. S. "Shuay Dagone" (Number of Visits 9)
 Tonnage, Gross 491 478 Built at Glenoch When built 1874
 Ditto, Net 293 312 Owners Burmah S. N. Co. Port belonging to Glenoch
 Diameter of Cylinder 34" & 42" Engines made by Caird & Co. When made 1874
 Length of Stroke 30" Boilers made by Ditto When made 1874
 Pressure of Steam 45 lbs. If Surveyed Afloat or in Dry Dock Pontoon & Aft. (State name of Dock.)
 Registered Horse Power 80. Years assigned. Character in Register Book. 100A1
 Last Survey No. _____ Port _____

Particulars of Repairs and Examination For S. S. No 2

(State cause of Repairs.)

Examined, cylinders, Slides & Valve faces found in good condition.
 Air, circulating Feed & Bilge examined: " " " "
 Crank Shaft & Thrust Bearing " " " "
 Boiler examined, a large riveted patch found at back end of Port furnace, several of the holes being cracked & recommended that a larger patch be fitted which has been done. Twelve new screw stays have been fitted at backs of Combustion chambers.
 Shell of Boiler found to be fairly good. Safety valve examined found to be in good condition & loaded to 45 lbs per sq. in.
 Recommended that the lever be eased in which has been done.
 Donkey Boiler examined a patch in mouth of furnace removed for examination of plate which was found to be fairly good. Safety valve examined found in good condition & loaded to 42 lbs per sq. in. This lever has been eased in.
 Vessel placed on Pontoon sea connections examined & found to be in good condition. Propeller & its connection found to be sound & the tail shaft a good working fit in Stern Bush.

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition renders the vessel eligible in my opinion to be marked with Lloyd's M. C. C. 82 — Provided that the Main Boiler be again examined within 12 mths. as per rule, & the donkey boiler also in 12 mths. on acct. of its age.

Entry or Registering Fee... £ 2 : : :
 (per Section 27.) 3/4/82
 Survey Fee (per Section 28) ... £ 5 : 5 : received by me, Geo. E. Milner
 Certificate (if required) ... £ : 2 : 6 1/4/1882
 to be sent as per margin.
 (Travelling Expenses, if any, £)

Committee's Minute

Tuesday, 4th June, 1882.

Lloyd's Ref 6, 12
Subject

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Lloyd's Register Foundation

LONG68-0345

It is submitted that this vessel
is eligible to have the notification
log No M.L. 6.82 recorded.
Subject to the Main boiler being
reinspected in 12 months as per rules
and the Donkey boiler in 12
months on account of its condition

D.S.

26/6/82



© 2021

Lloyd's Register
Foundation