

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office, 23/6/82)

No. 277 on the Machinery of the S. S. "Thomas Lea"
 Date, first Survey June 8th Last Survey June 20th 1882
 Survey held at London (Number of Visits 3)
 Tonnage, Gross 634 Built at Newcastle When built 1864
 Ditto, Net 406 Owners J. Fenwick & Son Port belonging to London
 Diameter of Cylinder 36 Engines made by T. & A. Eng. Works, Co. When made 1872
 Length of Stroke 28 Boilers made by Do. When made 1878
 Pressure of Steam 35 lbs. If Surveyed Afloat or in Dry Dock Pontoon & Aft. Classed A 1
 Registered Horse Power 80 (State name of Dock.)
 Last Survey No. Lloyd's M. C. 5.79. Port Lloyd's M. C. 5.79.

Particulars of Repairs and Examination Special Survey No 3.

(State cause of Repairs.)

Vessel placed on Pontoon sea connections examined & found to be in good condition. Propeller & its connections sound & the tail shaft down $\frac{1}{2}$ " in Stem bush. Examined cylinders, Slides Valve faces, Air, Circulating, Feed & Bilge pumps & valves, all found to be in good condition. Crank shaft examined, in good condition. Tunnel shafting examined found in good condition, three drain holes found in tunnel floor leading to After hold bilge, recommended that these be covered with a riveted plate which has been done. Boilers examined, found in good condition. — Safety valves examined found " " " & tested under steam to the working pressure of 35 lbs per sq. in. Direct spring valves.

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition, renders the vessel eligible in my opinion to be marked in the Register Book with Lloyd's M. C. 6.82.

Entry or Registering Fee... £ 1 : : :
 Survey Fee (per Section 27.) 24/6/82 £ 2 : 2 : : received by me, 7.7.8.
 Certificate (if required) ... £ : : : 17/7 1882
 to be sent as per margin.
 (Travelling Expenses, if any, £)

Committee's Minute

Assigned

Friday, 30th June, 1882

Geo. E. Milner
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2021

Lloyd's Register Foundation

LDN668-0432

(The Surveyors are requested not to write or below the space for Committee's Minute.)

(Insert Character, precisely as in the Register Book.)

It is submitted that this vessel
is eligible to run in as blassed
and have the notation
Lloyd's M. b. 6. 82 recorded

DJ
23/6/82



© 2021

Lloyd's Register
Foundation

Register of Survey for Repairs of Engines and Boilers